

Specifications of Apartment

FLOORING

- Vitrified tiles 600 x 600 mm in Drawing Room, Kitchen and Bedrooms
- Ceramic tiles 300 x 300 mm in Bathrooms and the Balconies

WALLS AND CEILING FINISH

POP finish walls & ceiling with OBD

KITCHEN

- Granite working top with stainless steel sink
- 2'-0" dado above the working top and 5'-0" from the floor level on remaining walls by ceramic tiles 300x450 mm
- Woodwork below the working top only box with shutter
- Individual RO Unit for drinking water make Ganga/Genx world or equivalent RO capacity 8 Ltr.

TOILETS

- Ceramic tiles 300 x 450 mm on walls up to door level
- White sanitary ware with EWC, CP fittings and mirrors in all toilets

DOORS & WINDOWS

- Outer doors and windows aluminum powder coated/UPVC
- Internal door frames made of Maranti or equivalent wood 90x50 mm
- Internal doors made of painted flush shutter 30 mm
- Main entry door frame of Maranti or equivalent wood with laminated flush shutter 32 mm
- Good quality hardware fittings



ELECTRICAL

 Copper wire in PVC conduits with MCB supported circuits and power and light points in wall & ceiling

TELEPHONE

Intercom Facilities



Disclaimer: All specifications, images including stock images, colours, pictures and accessories are indicative and used for illustrative



Specifications of Project

Total No. of Flats 1464 Nos.

EWS/LIG (Informal Sector) 1 No. (EWS-16 Nos.

LIG-25 Nos. & 79 Nos. Shop Saleable Area 1658.00 sqmt. /

17842.00 sqft.

No. of Floors 2Basements+Stilt/GroundFloor

+19 Floors/12 Floors

No. of Flats per Floor 8

No.of Lifts per Block. 3 (2 No-8 Passenger Lifts & 1

No-13 Passenger lift).

External Door MS Painted.

Internal Car Stainless Steel Wall & Granite

Stone Flooring.

Make Kone/Fujitec/Otis or Equivalent

Speed 1.5m/second

Entrance Lobby of Block

a. Ground Floor Entrance Lobby Area-

(65 sq.mt. /700 sq.ft.)

b. Lower & Upper Basement Lobby Area-

(48 sq.mt. / 515 sq.ft.)

c. Flooring-Vitrified Tiles

d. Ceiling - POP False Ceiling

e. Painting-OBD

f. Lift Facia - Tiles

g. Lighting - Ceiling Mounted Light Fixtures

h. Door - S.S. Doors

2. Staircase -

a. Flooring - Marble Stone Flooring (Staircase No-1).

Concrete / IPS Flooring (Staircase No.2)

b. Painting - OBD Paint.

c. Railing - MS Railing.

d. Lighting - Ceiling Mounted Light Fixture / Tube Lights

3. Terrace

a. Flooring – Tiles / Trimix Concrete

b. Painting - Texture Paint

c. Parapet - R.C.C/M.S Railing

d. Water Tank - R.C.C

4. Visitor's / Differently Able Toilet-

a. 1 in each Block-2.58 sq.mt./27sq.ft. Approx.

b. Flooring - Tiles

c. Painting - OBD

d. Wall Cladding - Tiles

e. W.C. - European WC

f. CP Fittings - Chrome Plated

5. Basement Area – Lower & Upper Basement.

a. Road & Parking - Trimix Concrete Flooring.

b. Lighting - Ceiling Mounted Light Fixture / Tube Lights

c. Parking size – 13.75 sgmt

6. Visitor Parking-

2 Visitors Parking for each Block

1 Disable person parking for each Block

9

7. Landscaping - (Total Area Approx. 11400 sq.mt./

122700 sq.ft.) which includes:

 Hard Landscape/RoadParking-Tiles/Trimix Concrete/Pavers/Kerb-Stone/Chequered Tiles

• Soft Landscape :- Natural Grass/Artificial Grass pad/

Grass Lawn/Shrubs/Plants/Trees

Lighting-Pole Light

Kids Play Area - 1 No.

(Parallel Bars-1 No./ Four Seater Seesaw Hugo-1 No./Triangular Climber Hugo- 1 No./Merry Go Round-1 No./ Fiero A Swing-1 No.)

Cricket pitch- 1 No.

Basketball Court – 1 No.

• Skating Rink-1 No.

Tennis court – 1 No.

Jogging Track.

Open air theatre with stage and sitting

Green Lawn

Pray Hall/Temple - 1 No.

a) SIZE - 36 SQM

b) FLOORING - TILES & MARBLE c) RAILING - MS RAILING

d) CEILING - POP PUNNING & PAINTS

8. ESS & DG (Maximum Capacity).

DG Sets-2000 KVA&Transformers - 4000 KVA

9. Online Solar Power System Of 50 KW Capacity

 Organic Waste Compost Plant(in basement) –approx.65 sq.mt./700 sq.ft.)

11. STP – 150 KLD – 2 Nos.(in basement) –approx. 500 sq.mt./5380 sq.ft.)

12. R.W.A Room – (in basement) –approx. 46.5 sq.mt./500 sq.ft.)

Flooring – Vitrified Tiles

Ceiling – Perforated gypsum false ceiling

Walls – OBD Paint

13. Maintenance Room – (in basement) –approx. 69.8 sq.mt./750 sq.ft.)

• Flooring – Vitrified Tiles

Ceiling – Perforated gypsum false ceiling

Walls – OBD Paint

14. L.T Panel Room - (on stilt) -approx. 83.7 sq.mt./ 900 sq.ft.)

Flooring – IPS

Walls – OBD Paint