

The amended plan duly approved
between Superceases all the earlier
approved plans.


THIS PLAN SHALL NOT BE CONSIDERED
AS PROOF OF OWNERSHIP FOR ANY
PURPOSE UNLESS IT IS ACCOMPANIED BY
DISPENSATION FROM THE L.A.M.

Approved as amended in Subject to the
conditions mentioned in this Office Letter
No. 141/05/2021 dated 14/05/2021.

COMMISSIONER
WILLYAM CITY MUNICIPAL CORPORATION
W.C. (Sd/-) 14/05/2021

Certified that the above permission is
issued by Commissioner V. V. V. V. V. V.

Deputy Director,
W.C.M.C. V. V. V.

BUILT - UP AREA DIAGRAM
FOR 8TH FLOOR
SCALE 1:250

BUILT-UP AREA CALCULATION			
FOR 8TH FLOOR			
RECT A = 27.75 X 38.40 = 912.00 SQ.M			
DEDUCTION			
1	8.100 X 29.150	=	236.12 SQ.M
2	2.450 X 2.250	=	5.51 SQ.M

DOORS & WINDOWS SCHEDULE

TYPE OF APERTURE	DESIGNATION	SIZE OF APERTURE	AREA INCLUSIVE OF FRAMES	AREA OF FIXED GLASS IF ANY
T.W. FLUSH DOOR	D1	1.00 X 2.10	2.10	NIL
T.W. FLUSH DOOR	D2	0.90 X 2.10	1.89	NIL
T.W. PANELED DOOR	D3	0.75 X 1.80	1.35	NIL
A.L.M. SLIDING WINDOW	W1	2.40 X 1.50	3.60	0.90
A.L.M. SLIDING WINDOW	W2	1.80 X 1.50	2.70	0.25
A.L.M. SLIDING WINDOW	W3	1.20 X 1.50	1.80	0.48
T.W. OVERHEAD WINDOW	V	0.60 X 0.90	0.54	0.54

LIGHT & VENTILATION STATEMENT

ROOM TYPE	SIZE OF ROOM	CARPET AREA	MINIMUM VENT. REQUIRED (1/6)	APERTURE OF ROOM	TYPE	AREA
LIVING	2.95 X 2.75	8.11	1.35	W	W	3.60
KITCHEN	2.75 X 2.15	5.91	0.99	W1	W1	2.70
BED	2.75 X 2.75	7.56	1.26	W2	W2	1.44
BATH	1.50 X 1.10	1.65	0.28	V	V	0.54
W.C.	0.90 X 1.25	1.13	0.19	V	V	0.54

DESCRIPTION OF PROPOSAL & PROPERTY

PROPOSED GROUP HOUSING SCHEME
AT VILLAGE : NILEMERE, TALUKA : VASAI DIST PALGHAR

NAME OF APPLICANT
SHRI. ANIL R. GUPTA

P.A. HOLDER

SIGNATURE OF APPLICANT

DATE

22/03/2021

DATE

22/03/2021

DATE

22/03/2021

DATE

22/03/2021

DATE

22/03/2021

DATE



Certified that the above permission is
issued by Commissioner V. V. V. V. V. V.

Deputy Director,
W.C.M.C. V. V. V.

COMMISSIONER
WILLYAM CITY MUNICIPAL CORPORATION
W.C. (Sd/-) 14/05/2021

THIS PLAN SHALL NOT BE CONSIDERED
AS PROOF OF OWNERSHIP FOR ANY
PURPOSE UNLESS IT IS ACCOMPANIED BY
DISPENSATION FROM THE L.A.M.

The amended plan duly approved
between Superceases all the earlier
approved plans.