

SLUM REHABILITATION AUTHORITY

Administrative Building, Pr. Anant Kanekar Marg, Bandra (East), Mumbai - 400 051

Intimation of Approval under Sub regulation 2.3 of Appendix - IV
of D.C.R. No. 33 (10) Dt. 15.10.97 of Brihanmumbai.

26 NOV 2020

No. SRA-ENG / K-E/PVT/0128/20060509/Composite Bldg.

Composite Building

To,
M/s. Sardar Realty
Sardar Dairy Compound,
Jijamata Marg, Pump House,
Andheri (East), Mumbai-400 093.

With reference to your Notice, letter No. 8531 dated 29/10/2020 and delivered
on 29/10/2020 and the plans, Sections, Specifications and Description and further particulars
and details of your building at CTS No. 380 & 380/1 to 96 of Village Mogara at
Jijamata Road, Jogeshwari (East), Mumbai in K/E Ward.


furnished to me under your letter, dated 29/10/2020 I have to inform you that the proposal
of construction of the building or work proposed to be erected or executed is hereby approved under
section 45 of the Maharashtra Regional & Town Planning Act, 1966 as amended up-to-date, subject to the
following conditions :

A. THAT THE FOLLOWING CONDITIONS SHALL BE COMPLIED WITH
BEFORE COMMENCEMENT OF THE WORK UPTO PLINTH LEVEL

- A.1) That the Commencement Certificate u/s. 44/69 (1) of the MR & TP Act, Shall be obtained before
starting the proposed work.
- A.2) That the compound shall be constructed, after getting the plot demarcated from the concerned
authority, on all sides of the plot clear of the road side drain without obstructing the flow of rain water
from the adjoining holding, to prove possession of holding before starting the work as per D.C.
Regulation No. 38 (27)
- A.3) That the structural Engineer shall be appointed, and the Supervision memo as per Appendix XI D.C.
Regulation 5(3) (ix) shall be submitted by him.
- A.4) That the Structural design and calculations for the proposed work accounting for system analysis as
per relevant I.S. code along with plan shall be submitted before C.C.

Subject to your so modifying your intention as to comply the aforesaid mentioned conditions and meet by requirements. You will be at liberty to proceed with the said building or work at anytime before the _____ day of _____ 20 but not so as to contravene any of the provisions of the said Act as amended as aforesaid or any rule, regulations of bye-law made under that Act at the time in force.

Your attention is drawn to the special Instructions and Notes accompanying this Intimation of Approval


25/11/2020
Executive Engineer, (S.R.A.)

SPECIAL INSTRUCTIONS

- (1) IN CASE OF PRIVATE PLOTS THIS INTIMATION OF APPROVAL GIVES NO RIGHT TO BUILD UPON LAND WHICH IS NOT YOUR PROPERTY.
- (2) Under Section 151 & 152 of M.R & T.P. Act 1966, as amended the Chief Executive. Officer, Slum Rehabilitation Authority has empowered the Chief Engineer (S.R.A.)/ Executive Engineer (S.R.A.) to exercise, perform and discharge the powers, duties and functions conferred and imposed upon and vested in the C.E.O. (S.R.A.) by section of the said Act.
- (3) Proposed date of commencement of work should be communicated to this office.
- (4) One more copy of the block plan should be submitted to the Collector, Mumbai / Mumbai Suburbs District as the case may be.
- (5) Necessary permission for Non-agricultural use of the land shall be obtained from the Collector, Mumbai / Mumbai Suburban District before the work is started. The Non-agricultural assessment shall be paid at the rate that may be fixed by the Collector, under the Land Revenue Code and Rules thereunder.

Attention is drawn to the notes Accompanying this Intimation of Approval.

- 5) That the minimum plinth height shall be 30 cm. above the surrounding ground level or in areas subject to flooding the height of plinth shall be at least 60 cm. above the high flood level.
- 6) That the low lying plot shall be filled up to a reduced level of atleast 92 T.H.D. or 15 cm. above adjoining road level whichever is higher with murum, earth, boulders etc. and shall be leveled, rolled, consolidated and sloped towards road.
- 7) That the internal drainage layout shall be submitted & got approved from concerned Asst. Engineer (SRA) and the drainage work shall be executed in accordance with the approved drainage layout.
- 8) That the existing structure proposed to be demolished shall be demolished with necessary phase program by executing agreement with eligible slum dwellers.
- 9) That the Registered site supervisor through Architects/Structural Engineer shall be appointed before applying for C.C. & quarterly report from the site supervisor shall be submitted through the Architect/Structural Engineer certifying the quality of the construction work carried out at various stages of the work.
- 10) That no construction work shall be allowed to start on the site unless labour insurance is taken out for the concerned labours and the same shall be revalidated time to time. And the compliance of same shall be intimated to this office.
- 11) The Structural designs and the quality of materials and workmanship shall be strictly as per conditions laid down in Regulation 49 of DCPR 2034 amended up to date.
- 12) That you shall submit the NOC's as applicable from the following concerned authority in the office of Slum Rehabilitation Authority at a stage at which it is insisted upon by the concerned EE (SRA).

Sr. No.	NOC's	Stage of Compliance
1.	A.A. & C. K/East Ward	Before Plinth CC.
2.	H.E. from MCGM	Before Plinth CC.
3.	Tree Authority	Before Plinth CC.
4.	Dy. Ch. Eng. (SWD) Regarding Internal SWD	Before Further CC.
5.	Dy. Ch. Eng.(S.P.) (P & D)	Before Plinth CC.
6.	Dy.Ch.Eng.(Roads) W.S.	Before Plinth CC.
7.	P.C.O.	Before Plinth CC.
8.	BEST / TATA / Reliance Energy / MSEB / Electric Co.	Before Further CC.
9.	E.E. (M&E) of MCGM	Before Further CC.
10.	E.E. (T&C) of MCGM for Parking Layout	Before Plinth CC.

11.	Revised Civil Aviation NOC	Before Approval of Amended Plans in lieu of additional height approved vide in Concessions.
-----	----------------------------	---

- 13) That the design and construction of the proposed building will be done under supervision of Registered Structural Engineer as per all relevant I. S. Codes including seismic loads, fire engine loads, precautions for submerged structural members as well as under the supervision of Architect and Licensed Site Supervisor.
- 14) That Revision in LOI/Parameters due to changes proposed in Building u/r shall be got approved before asking any permission for Sale Component of the Scheme.
- 15) That the developer shall ensure compliance of the provision of building and other construction workers (Regulation & Employment and condition of service) Act, 1996 and submit documentation to that effect in order to comply various orders of Hon'ble Supreme Court of India in 1A 127961/2018 on SWM (c) No(s) 1/2015.
- 16) That the construction work shall not be carried out between 10.00 PM to 6.00 AM, in accordance with the Rule 5A(3) of Noise Pollution (Regulation & Control) Rules 2000 and provision of Notification issued by MOE & F Deptt.
- 17) That you shall submit undertaking stating therein that, adequate safety measure shall be taken during entire construction activity as per the recommendations of registered Structural Consultant & Geotechnical Consultant & or any other Consultant required as per specific site conditions. The entire responsibility in this regard shall vest with developer.
- 18) That you shall abide with all the proceedings/orders of court of Law or any judicial/cosy judicial forums arising out of S. R. Scheme under reference if any. You shall submit proposals by taking due cognizance of it from time to time.
- 19) That carriage entrance over existing SWD shall be provided if required and charges if any for the same shall be paid to MCGM before requesting occupation.
- 20) That all the Conditions of LOI issued on 22/10/2020 shall be complied as per the stages mentioned therein.

B. THAT THE FOLLOWING CONDITIONS SHALL BE COMPLIED WITH BEFORE FURTHER C.C. OF SUPER STRUCTURE:

- 1) That a plan showing the dimensions of the plinth and the available open spaces certified by the Architect shall be submitted and the same shall be got checked by this office staff.

- 2) That the stability certificate for work carried out upto plinth level/stilt level shall be submitted from the Lic. Structural Engineer.
- 3) That the quality of construction work of bldg. shall be strictly monitored by concerned Architect, Site supervisor, Structural Engineer, Third Party Quality Auditor and periodical report, stage wise on quality of work carried out shall be submitted by Architect with test result.
- 4) That you shall submit NOC for Environmental Clearance (if applicable) for the project as per MOE & F, New Delhi's Notification issued under No. S.O.1533 dated 14/09/2006, under sub rule (3) of rule 5 Environment (Protection) Rules 1986, as directed by NGT on 03/12/2018 under orders No. O.A. No. 1017/2018 before commencing the construction beyond 20000.00 Sq.Mts, as per this office Circular No. 136.

C. THAT THE FOLLOWING CONDITIONS SHALL BE COMPLIED WITH BEFORE GRANTING O.C. TO ANY PART OF THE PROPOSED BUILDING:

- 1) That all the Conditions of LOI issued on 22/10/2020 shall be complied as per the stages mentioned therein and Completion certificate if any shall also be submitted requisite at appropriate stage, before OC.
- 2) The Building Completion Certificate in prescribed Performa certifying work carried out as per specification shall be submitted.
- 3) That some of the drains shall be laid internally with C.I. pipes.
- 4) That you shall develop the layout access/D.P. Road/setback land including providing streetlights as per the remarks/specifications MCGM. And submit the completion certificate from E.E. (Road Construction) as per the remarks.
- 5) That the dustbin shall be provided as per requirement.
- 6) That carriage entrance over existing SWD shall be provided and charges if any for the same shall be paid to MCGM before requesting occupation.
- 7) That the surface drainage arrangement shall be provided in consultation with E.E. (SWD) as per the remarks and a completion certificate shall be obtained and submitted before requesting for occupation certificate/ B.C.C.
- 8) That the requirements from the M.T.N.L./ Reliance Energy /concerned electric Supply Co. shall be complied and complied with before asking occupation permission.

- 9) That the Architect shall submit the debris removal certificate before requesting for occupation permission.
- 10) That Min. 10'-0" wide paved pathway up to staircase shall be provided.
- 11) That the surrounding open spaces, parking spaces and terrace shall be kept open and unbuilt upon and shall be levelled and developed before requesting to grant permission to occupy the building or submitted the B.C.C. whichever is earlier.
- 12) That the name plate/board showing Plot No., Name of the Bldg. etc. shall be displayed at a prominent place.
- 13) That the N.O.C. from Inspector of Lifts, P.W.D. Maharashtra, shall be obtained and submitted to this office.
- 14) That the drainage completion Certificate from E.E. (S.P.) (P & D) for provision of septic tank/soak pit/STP shall be submitted.
- 15) That stability Certificate from Structural Engineer in prescribed Performa 'D' along with the final plan mounted on canvas shall be submitted.
- 16) That the single P.R. cards for the amalgamated plot shall be submitted.
- 17) That layout R.G. shall be developed as approved by SRA.
- 18) That the N.O.C. from the A.A. & C. P/North Ward shall be obtained and the requisitions, if any shall be complied with before O.C.C.
- 19) That the allotment list of slum dweller to be accommodated in the building as per lottery conducted by A.R.S. shall be submitted in duplicate before submitting OCC.
- 20) That completion certificate from C.F.O. shall be submitted.
- 21) That you shall submit P.R. Card and CTS plan thereby clearly earmarking the rehab plot and sale plot and built up area as per the approved plans/layout.
- 22) That the completion certificate from E.E. (T&C) of MCGM for parking shall be submitted.
- 23) That the completion certificate from E.E. (M&E) of MCGM for Ventilation/ Stack parking/Mechanical Parking System shall be submitted.
- 24) That the completion certificate from Tree Authority of MCGM shall be submitted.
- 25) That you shall submit the receipt for handing over of buildable/road/ non-buildable reservations before requesting full OCC of sale bldg.


- 26) That the Rain Water Harvesting system should be installed/provided as per the direction of U.D.D., Govt. of Maharashtra under No. TPB/432001/2133/CR-230/01/UD-11 dtd. 10/03/2005 and the same shall be maintained in good working conditions all the time, failing which penalty of Rs.1000/- per annum for every 100 sq.mt. of built-up area shall be levied.

D. THAT THE FOLLOWING CONDITIONS SHALL BE COMPLIED WITH BEFORE B.C.C.

- 1) That certificate under Section 270A of B.M.C. Act shall be obtained from H.E.'s department regarding adequacy of water supply.
- 2) That you shall have to maintain the rehab building for a period of 3 years from the date of granting occupation to the rehab bldg.
- 3) That you shall have to maintain the electro mechanical systems such as water pumps, lifts, etc. for a period of ten years from the date of issue of Occupation Certificate to the Rehabilitation / Composite building.

NOTES:

1. That C.C. for sale building shall be controlled in a phasewise manner as decided by CEO (SRA) in proportion with the actual work of rehabilitation component as per Circular No. 98 & 104.
2. That no occupation permission of any of the sale wing/sale building/sale area shall be considered until Occupation Certificate for equivalent Rehabilitation area is granted.
3. That CEO (SRA) reserves right to add or amend or delete some of the above mentioned conditions if required, during execution of Slum Rehabilitation Scheme.


25/11/2020
Executive Engineer - V

Slum Rehabilitation Authority

NOTES

- (1) The work should not be started unless objections _____ are complied with.
- (2) A certified set of latest approved plans shall be displayed on site at the time of commencement of the work and during the progress of the construction work.
- (3) Temporary permission on payment of deposit should be obtained for any shed to house and store for constructional purposes, Residence of workmen shall not be allowed on site. The temporary structures for storing constructional materials shall be demolished before submission of building completion certificate and a certificate signed by Architect submitted alongwith the building completion certificate.
- (4) Temporary sanitary accommodation on full flushing system with necessary drainage arrangement should be provided on site for workers, before starting the work.
- (5) Water connection for constructional purposes will not be given until the hoarding is constructed and application is made to the Ward Officer of M.C.G.M. with the required deposit for the construction of carriage entrance, over the road side drain.
- (6) The owners shall intimate the Hydraulic Engineer of M.C.G.M. or his representative in wards of M.C.G.M. atleast 15 days prior to the date of which the proposed construction work is taken in hand that the water existing in the compound will be utilised for their construction works and they will not use any Municipal Water for construction purposes. Failing this, it will be presumed that Municipal tap water has been consumed on the construction works and bills preferred against them accordingly.
- (7) The hoarding or screen wall for supporting the depots of building materials shall be constructed before starting any work even though no materials may be expected to be stabled in front of the property. The scaffoldings, bricks, metal, sand, preps, debris etc. should not be deposited over footpaths or public street by the owner/architect/their contractors, etc. without obtaining prior permission from the Ward Officer of the area.
- (8) The work should not be started unless the compliance of abovesaid conditions is approved by this department.
- (9) No work should be started unless the structural design is submitted from LSE.
- (10) The work above plinth should not be started before the same is shown to this office Sub-Engineer (SRA) concerned and acknowledgement obtained from him regarding correctness of the open spaces dimension.
- (11) The application for sewer street connections, if necessary, should be made simultaneously with commencement of the work as the Municipal Corporation of Greater Mumbai will require time to consider alternative site to avoid the excavation of the road and footpath.
- (12) All the terms and conditions of the approved layout/sub-division/Amalgamation under No. _____ should be adhered to and complied with.
- (13) No building/Drainage Completion Certificate will be accepted and water connection granted (except for the construction purposes) unless road is constructed to the satisfaction of the concerned Ex. Engineer of M.C.G.M. and as per the terms and conditions for sanction to the layout.
- (14) Recreation ground or amenity open space should be developed before submission of building Completion Certificate.
- (15) The access road to the full width shall be constructed in water bound macadam before commencing work and should be complete to the satisfaction of concerned. Ex-Engineer of M.C.G.M. including asphaltting, lighting and drainage before submission of the building Completion Certificate.
- (16) Flow of water through adjoining holding or culvert, if any should be maintained unobstructed.
- (17) The surrounding open spaces around the building should be consolidated in concrete having broken glass pieces at the rate of 0.125 cubic metres per 10 Sq.Mtrs below pavement.

- (18) The compound wall or fencing should be constructed clear of the road widening line with foundation below level of the bottom of road side drain without obstructing flow of rain water from adjoining holding before starting the work to prove the owner's holding.
- (19) No work should be started unless the existing structures or proposed to be demolished are demolished.
- (20) If it is proposed to demolish the existing structures by negotiations with the tenants, under the circumstances, the work as per approved plans should not be taken up in hand unless the Chief Engineer [SRA] is satisfied with the following :
 - (i) Specific plans in respect of evicting or rehousing the existing tenants on your plot stating their number and the area in occupation of each.
 - (ii) Specifically signed agreement between you and the existing tenants that they are willing to avail for the alternative accommodation in the proposed structure.
 - (iii) Plans showing the phase programme of construction has to be duly approved by this office before starting the work so as not to contravene at any stage of construction, the Development Control Rules regarding open spaces, light and ventilation of existing structure.
- (21) In case of additional floor no work should be started during monsoon which will give rise to water leakage and consequent nuisance to the tenants staying on the floor below.
- (22) The bottom of the over head storage work above the finished level of the terrace shall not be more than 1 metre.
- (23) The work should not be started above first floor level unless the No Objection Certificate from the Civil Aviation Authorities, where necessary, is obtained.
- (24) It is to be understood that the foundations must be excavated down to hard soil.
- (25) The positions of the nahanis and other appurtenances in the building should be so arranged as not to necessitate the laying of drains inside the building.
- (26) No new well, tank, pond, cistern or fountain shall be dug or constructed without the previous permission in writing from the Chief Executive Officer of Slum Rehabilitation Authority.
- (27) All gully traps and open channel shall be provided with right fitting mosquito proof covers as per relevant I. S. specifications.
- (28) No broken bottle should be fixed over boundary walls. The prohibition refers only to broken bottles & not to the use of plain glass for coping over compound wall.
- (29) If the proposed addition is intended to be carried out on old foundations and structures, you will do so at your own risk.


 Executive Engineers, (S.R.A.)