


[illegible]

21.2.5 ADDITIONAL PARKING FOR LOADING & UNLOADING 3.5 M X 7.50 M FOR EACH 1000 SOLID AREA 2816.71/1000 = 2.82 NOS. Sd 3 OF 5 M FOR LOADING & UNLOADING

PORTABLE FIRE EXTINGUISHERS – (AS PER G.D. CLAUSE 24.22.1)

ONE UNIT OF 6 KG. DRY CHEMICAL POWDER (D.CP). ONE UNIT OF 4.58 KG. OF CO2 SHALL BE PROVIDED FOR EVERY 1000 SQMTS. OF BUILT-UP AREA AT EACH FLOOR.

MOSQUITO PROOF WATER TANK

WATER STORAGE TANK SHALL BE MAINTAINED THAT PERFECTLY MOSQUITO-PROOFED. BY PROVIDING A PERFECTLY FITTING HINGED COVER AND EVEN FITTING HINGED COVER AND EVERY TANK MORE THAN 1.50 MTS. IN HEIGHT SHALL BE PROVIDED WITH A PERMANENTLY FIXED IRON LADDER TO ENABLE INSPECTION BY ANTI-MALARIA STAFF.

DRAINAGE CERTIFICATE-

THE DEPTH POSITION EX. MIN. MIN. IS SHOWN & VERIFIED PERSONALLY BY ME ON SITE FORMED CAN BE USED CONNECTION AS CHAKEN IN PLAN.

CERTIFICATE-

ENGINEER IS FULLY RESPONSIBLE FOR OPEN LEAVING. MARGINAL SPACE AND ROAD LINE PORTION.

CERTIFIED THAT THE PLOT UNDER REFERENCE WAS SURVEYED BY ME ON AND THE DIMENSIONS OF SIDES ETC. OF PLOT STATE ON PLAN ARE AS MEASURE ON SITE AND THE AREA SO WORKED OUT WITH THE AREA STATED IN DOCUMENT OF OWNER SHIP P.T RECORD.

NOTE:- IT IS CERTIFY THAT THE PLOT IS SURVEYED BY ME ON ALL DIMENSION SITES SHAPE AND ARE SHOWN ON PLAN TALLIES WITH AN ESTATE PORTION OF OCCURRENCE AS AN ENGINEER AM FULLY RESPONSIBLE FOR THAT AS AN ENGINEER CERTIFY THAT ALL REQUIREMENTS UNDER G.D. CLAUSE 4.2.2 HAS BEEN VERIFIED BY ME AND THE SITE LAND IS SUITABLE FOR PROPOSED CONSTRUCTION. THE PLOT DIMENSIONS AS SHOWN IN THE PLAN CORRESPONDS WITH THE SITE.

PARKING AREA CALCULATION-		IN SQ MT
REQ PARKING 10 % OF PLOT AREA		
PLOT AREA = 47350 SQ MT		
REQ PARKING - 47350 x 10 % = 47350 SMT		
REQ CAR PARKING 50 %	REQ	236.75
REQ TWO VEHICAL PARKING 50 %	REQ	237
TOTAL		473.50
PROP CAR PARKING		
IN MARGIN (1) 1/27 82.17 = 7.89X3.50		= 181.50 SQ
IN MARGIN (2) 3.16 X 6.77		= 21.39 SQ
IN MARGIN (3) 5.27 X 2.50		= 13.18 SQ
IN MARGIN (4) 6.00 X 3.00		= 18.00 SQ
TOTAL		= 237.07 SQ
PROP. OTHERS PARKING		
IN MARGIN (1) 48.84 X 1.50		= 73.22 SQ
IN MARGIN (2) 15.0 X 4.8 X 3		= 22.19 SQ
IN MARGIN (3) 16.72 X 1.50		= 25.08 SQ
IN MARGIN (4) 5.54 X 2.0 X 7		= 77.56 SQ
IN MARGIN (5) 2.77 X 1.50		= 4.16 SQ
IN MARGIN (6) 15.0 X 5.88 X 2		= 17.04 SQ
IN MARGIN (7) 1.29X2.84 X 3.43X1.50		= 5.90 SQ
IN MARGIN (8) 20.5 X 4.0 X 2.17		= 0.69 SQ
IN MARGIN (9) 10.54 X 1.50		= 15.81 SQ
IN MARGIN (10) 1.23 X 9.4 X 1.29X3.00		= 12.15 SQ
IN MARGIN (11) 12.42 X 6.5 X 3.06		= 3.90 SQ
TOTAL		= 239.29 SQ

BUILT UP AREA TABLE - (IN SQ MI)					F.S.T. AREA TABLE - (IN SQ MI)				
BLOCK	GR.FL	MAZZ.FL	FR.FL	TOTAL	BLOCK	GR.FL	MAZZ.FL	TOTAL	
A	1078.39	336.16	-	1414.55	A	1078.39	336.16	1414.55	
B	1311.92	408.11	-	1720.03	B	1311.92	408.11	1720.03	
C	26.54	-	- 18.23	44.77					
TOTAL	2416.85	744.27	18.23	3179.35	TOTAL	2390.31	744.27	3134.58	

CARPET AREA (IN SQ MT)		TENAMENT & FLOOR AREA TABLE :- (IN SQ MT)			
BLOCK	TOTAL F.A.	BLOCK	USE	EQ.TENA.	TOTAL F.A.
A	1280.91	A	IN SHED	21	1280.91
B	1537.80	B	IN SHED	24	1537.80
TOTAL	2818.71	TOTAL		45	2818.71

	TOTAL	2016-71			2016-71
			SANITARY AREA CALC:-		
			TOTAL CARPET AREA = 2818.71		
			REQ. 1 USERS FOR EACH 25 SQMT CARPET AREA		
			2818.71 SMT/ 25	=	112.75 SAY 113 USERS
			REQ. 1 W.C. PER GENDER		




LAYOUT PLAN SHOWING PROPOSE INDUSTRIAL BUILDING ON F.P. NO.:- 92+95/2 OF T.P.S. NO.:- 107, (RAMOL) (DRAFT SANCTIONED) [R.S. NO.:- 667+671/2, O.P.NO.:- 92+95/2], MOJE - RAMOL, TA - VATVA, DIST- AHMEDABAD.				SHEET NO.:- 1/6
SCALE :- 1 CM = 2.00 MT	ZONE :- INDUSTRIAL ZONE GENERAL (I.G.)	USE :- INDUSTRIAL SHED	BLOCK :- A	
AREA TABLE :			IN SQMT	

PLAT AREA OF P.P. NO: - 92+99/2	4735.00
PROP. B.A. ON GROUND FLOOR	2416.85
PROP. B.A. ON MAZZANINE FLOOR	744.27
PROP. B.A. ON FIRST FLOOR	18.23
TOTAL PROP. BUILDUP AREA	3719.35
PERM. FLOOR AREA (1735 SQ.M + 98%)	3735.35

PERMIT F.S.I. (1:1) (4/35.00 X 1.00)	4735.00
PROP. F.S.I. AREA OF GR. FL.	2390.31
PROP. F.S.I. AREA OF MAZZANINE FL.	744.27
TOTAL F.S.I. AREA	3134.58
BALANCE F.S.I. AREA	1600.42

TREE PLANTATION CALC :- SQ MT REQ.TREE 200 SMT = 5 NOS. 4735.00X5/200 SMT = 118.38 NOS. SAY REQ.TREE = 119 NOS. PROVIDE TREE = 119 NOS.	CONTAINER BIN CALCULATION:- NOS. TOTAL FLOOR AREA = 2818.71 SQ MT REQ. FL. AREA /100 = 2818.71/100 28.19 X 20 = 563.80 LTR MAXI. CAPACITY OF CONTAINER 80 LTRS 563.80/80 = 7.05 NOS. SAY 08 NO. REQ.
---	---

PERCOLATION WELL CALC:- NOS.	PROVIDE 08 NOS. CONTAINER	
	COLOUR NOTE :-	
REQ.P.WELL	F.P. BOUNDARY	P. WELL
1500 TO 4000 SMT = 1.00 NOS.	PROP. WORK	TREE
4735/00/ 4000.00 = 1.18 NOS.	PARKING	C.B.
SAY REQ P.WELL = 2 NOS.	ROAD DRAIN	ROAD



ENAGAR
App.ID: 003 PP 19 2000 6
ODPS ID: 00P5 / 2019 00 2
Dt.: 29 / 8 / 2020
BPSP, TDO, AMC

commencement Certificate (Rajachittihalli)

Raja Chithhi Number : - 03673/019920/A3835/R0/M/1

Date: 03.09.2020

(Signature) 03.09.2020

T.D Sub Inspector (B.P.S.P.) T.D Inspector (B.P.S.P.) Asst. T.D.O. (B.P.S.P.)

AUTHORITY

AIR VENT

PERFORATED R.C.C SLAB

CATCH PIT WITH FILTRATION MEDIA

SIZE- 200*200 D X 2.50 M

COARSE SAND 300 mm

PEA GRAVEL 300 mm

GRAVEL 300 mm

800 MM DIA. P.V.C. PIPE

250 MM DIA. STRAINER PIPE


125 MM DIA. GRAVEL PACKING

STRAINER

PERCOLATION WELL (NOT TO SCALE)



D- UP TO UNDER GROUND II (SECOND POWER LAQUER)

D- UP TO UNDER GROUND I (10.00 M)



BUILT UP	AREA
BLOCK	GR FL
A	1078.39
B	1311.92
C	26.54
TOTAL	2416.85

LAY OUT PLAN SHOWING PROPOSE INDUSTRIAL BUILDING ON P.P. NO. - 92+95/2 OF T.P.S. NO. 107, (RAMOL) (DRAFT SANCTIONED) R.S. NO. 667+67/2, O.P.NO. - 92+95/2/2, MOJE :- RAMOLI, TA :- VATVA, DIST.- AHMEDABAD.			SHEET NO. - 1/6
SCALE : 1 CM = 2.00 MT	ZONE : INDUSTRIAL ZONE GENERAL (I.G.)	USE :- INDUSTRIAL SHED	BLOCK - B
AREA TABLE :		IN SOMIT	
PLOT AREA OF P.P. NO. - 92+95/2		4735.00	
PROP. B.A. ON GROUND FLOOR		2416.85	
PROP. B.A. ON MAZZANINE FLOOR		744.27	
PROP. B.A. ON FIRST FLOOR		18.23	
TOTAL PROP. BUILDUP AREA		3179.35	
PERMI. F.S.I. (1-1) (4735.00 X 1.00)		4735.00	
PROP. F.S.I. AREA OF GR. FL.		2390.31	
PROP. F.S.I. AREA OF MAZZANINE FL.		744.27	
TOTAL F.S.I. AREA		3134.58	
BALANCE F.S.I. AREA		1600.42	
TREE PLANTATION CALC. :- SQ MT		CONTAINER BIN CALCULATION:- NOS.	
REQ. TREE 200 SMT = 5 NOS.		TOTAL FLOOR AREA = 2818.71 SQ MT	
4735.00X5/200 SMT = 118.38 NOS.		REQ. FL. AREA = 2818.71/100	
SAY REQ. TREE = 119 NOS.		28.19 X 20 = 563.80 LTR	
PROVIDE TREE = 119 NOS.		MAXI. CAPACITY OF CONTAINER 80 LTRS	
		563.80/80 = 7.05 NOS. SAY 8 NOS. REQ.	



૧૪/૦૨/૨૦૧૭/૬૩૩૫/૧૧ ડા-૧૬-૧૧-૧૦ ના પદ ચલુત્તર બાંધકામની
 ૧૪મી મુકાબી શરૂ.

SYSTEM/WORK RELEASE NO.: 20200903-00200100, ON DT.: 20/12/2019
MADE ON RECEIPT NO.: 20200903-00000518-29000006-0002, 20200903-
20200903-00000518-29000006-0004 ON DT.: 03/09/2020

(6) THIS CASE HAS BEEN SCRUTINIZED AND APPROVED BY BUILDING
ON DT.: 27/08/2020

(7) PERMANENT PROVISION ON THE SITE FOR WASHING AND CLEANING
THE VEHICLES/DUMPER/EQUIPMENTS GOING AND GOING ON
OTHERWISE ANY ACTION WILL BE TAKEN AND OWNER AND
SOLELY RESPONSIBLE FOR ANY DAMAGE OR SPOIL OF PUBLIC ROAD
NATURALLY DEVELOPMENT PERMISSION IS GIVEN ON THE

(13) ALL RELEVANT TERMS AND CONDITIONS MENTIONED IN A 2004/11/01, ORDER NO. 11-04/11-01-2004/001, 320- 63007320/01 (AHMEDABAD) IT IS SUBMITTED BY OWNER-APPLICANTS, AND NOT TO BE GIVEN BY OWNER-APPLICANTS AND ARCHITECTS. THE SAME WILL BE APPLICABLE AND BINDING TO OWNER/APPLICANT.

(13) THIS PERMISSION IS GIVEN ON THE BASIS OF OPINION FOR PL DIVISIONAL SUPERINTENDENT (PROPERTY TAX DEPT., E.Z.) ON PT.

(14) THIS PERMISSION IS GIVEN ON THE BASIS OF KASBA KARNATA.E.O.(E.Z.) ON DT. 09/09/2019.

(15) APPLICANT SHALL HAVE TO MAKE PROVISION FOR ROOFTOP INSTALLATION AND MAINTENANCE AS PER CL. 17.6.3 OF THE APPLICANT/ DEVELOPER/ ARCHITECT/ ENGINEER/ STRUCTURE

[illegible]

કચ્છા પહિલનાં પાલવરુની જાણવતી પહેલા તમામ પાલવર/પહોળોન સમગ્રી રીકોર
તેમજ તે કુળજ લતાવા અજરારર/રેડીયોલર તા- ૩૧/૧૨/૨૦૧૯ તા સેજ અરોપ
પહોળી
(રેડીયોન) અને આના બાંધકામ કમપીઓ/સેલરનીનુ નિયમન અને નોકરીની સેવાતો
રેડી નોકરી બાંધકામ પછીને સુર કરવાના ૩૦ રીયામ પછીને સુદર તારાતરો
નોકીલ તેજ પાલવરનુ કમ રૂમની ૩૦ રીયામો રીકોર કરતા રેડીન સુદરની નોપા
સમગ્રની અને પહોળીની રીકોર જાણવતીની રેડી
(રેડીયોન) રેડીના પહોળર (COVID-19) સેકમજ પહોળવાન સમગ્રી રેડીસાગી
વાતરોનુ પહોળર/પહોળર રેડી રેડી રેડીસાગીના તમામ નિયામોનુ મુલાકાતી પાલવર
પહોળી

ENAGAR
 App.ID: 001 BDP 9200087
 ODPs ID: ODPs/2019/002122
 Dt.: 29/8/2020
 BPSP, TDO, AMC

PERCOLATION WELL CALC:- NOS.		COLOUR NOTE :-	
REQ P.WELL		F.P. BOUNDARY	P. WELL
1500 TO 4000 SMT = 1.00 NOS.		PROP. WORK	TREE
4735.00/ 4000.00 = 1.18 NOS.		PARKING	C.B.
SAY REQ P.WELL = 2 NOS.		PROP. DRAIN	ROAD
PROV. P.WELL = 2 NOS.			

NOTE:-

IT IS CERTIFIED THAT PLOT UNDER REFERENCE IS SURVEYED BY ME AND THE DIMENSIONS OF ALL SIDES OF PLOT AND PLOT AREA AS SHOWN IN PLAN ARE MEASURED BY ENGINEER ON RECORD AND IN ACCORDANCE WITH OWNERSHIP / REVENUE RECORD.

- ENGINEER IS FULLY RESPONSIBLE FOR LEAVING OPEN SPACE AND MARGIN.
- THE DEPTH AND POSITION OF EXISTING MUNICIPAL MANHOLE IS VERIFIED BY ME ON SITE AND PREMISES CAN GET DRAINAGE CONNECTION.
- IT IS CERTIFY THAT ACCORDING TO CGOBR-2017 ALL REQUIREMENTS OF THE BUILDINGS ARE CHECKED AND NECESSARY ACTIONS ARE TAKEN.
- IT IS CERTIFY THAT ACCORDING TO THE CLAUSE NO. - 4.4.3 OF THE CGOBR-2017 THE STRUCTURE OF THE BUILDING IS DESIGN AS PER THE NORMS OF THE INDIAN STANDARDS.
- DESIGN OF STAIRCASE AND RAILING IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 13.1.1.1 AND 13.1.1.3 OF CGOBR-2017.
- PEDESTRIANS RAMP IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 13.1.1.4 OF CGOBR-2017.
- ELECTRICAL INFRASTRUCTURE SHALL BE PROVIDED AS PER CLAUSE NO. 13.1.1.7 OF CGOBR-2017.
- DRINKING WATER FACILITY FOR DISABLED PERSONS IS PROVIDED AS PER THE CLAUSE NO. 13.6.2 OF CGOBR-2017.
- DRAINAGE FACILITY IS PROVIDED AS PER THE CLAUSE NO. 13.10 OF CGOBR-2017.
- SIGNAGES OF THE PARKING PLACE IS TO BE PROVIDED AS PER THE PROVISION OF THE CLAUSE NO.-13.7 OF CGOBR-2017.
- ENTRANCE OF THE BUILDING IS PROVIDED AS PER THE CLAUSE NO. 13.1.3.1 OF CGOBR-2017.
- THE PAVING OF BUILDING UNDERGROUND PLOT AS PER THE PROVISION OF THE CLAUSE NO. -13.11.3 OF CGOBR-2017.
- THE STRUCTURE DESIGN OF THE BUILDING IS AS PER THE NORMS OF THE SPECIFIED IN THE INDIAN STANDARD AND TAKE NECESSARY ACTION SHALL BE TAKEN FOR THE STRUCTURAL SAFETY DURING CONSTRUCTION.
- RAIN WATER STORAGE TANK AND TANK WATER HARVESTING SYSTEM SHALL BE PROVIDED AS PER CLAUSE NO. -17.2 OF CGOBR-2017.
- COMMUNITY HALL PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. -17.2.4 AND 17.2.5 OF CGOBR-2017.
- TREE PLANTATION IS PROVIDED AS PER THE CLAUSE NO. -17.4 OF CGOBR-2017.
- MAINTENANCE AND UPGRADEDATION OF BUILDING IS AS PER CHAPTER NO.-19 OF CGOBR-2017.
- ROOF TOP SOLAR ENERGY INSTALLATION A GENERATION SHALL BE PROVIDED AS PER CLAUSE NO. -17.5.1 OF CGOBR-2017



For, RUDRA BUILDCON

[Signature]

Partner

[illegible][illegible]

Ahmedabad Municipal Corporation
 ENAGAR APPLICATION No - 0018BDP19200087
 ODPS Application ID - ODPS20190010222
 Case No - BLNTIC2019000020C/RVA/33836/R0/M1
 This Development permission has been granted office for the ODPS (Online Development Permission System), ENAGAR above reference case vide Notification No. PRCCH/102019/184, Dtd.20/06/2019 of Urban Development and Urban Housing Department, Government of Gujarat and directions issued by Competent Authority from time to time, under provision of Comprehensive General Development Control Regulations-2017.
 Plan approved as per terms and condition mentioned in the commitment Certificate (Rajachithli)
 Rajachithli Number :- 03674010920/A3836/R0/M1
 Date: 03.07.2020
 T.D.U. Inspector T.D. Inspector Asst.T.D.O.
 23.07.2020 23.07.2020 23.07.2020

[illegible][illegible]

PERCOLATION WELL CALC- NOS.	COLOUR NOTE:-
REQ P WELL	P. BOUNDARY P. WELL
1500 TO 4000 SMT = 1.00 NOS.	PROP. WORK TREE
4735.00/ 4000.00 = 1.18 NOS.	PARKING C.B.
SAY REQ P WELL = 2 NOS.	PROP. DRAIN. ROAD
PROV. P WELL = 2 NOS.	
NOTE:- - IT IS CERTIFIED THAT PLOT UNDER REFERENCE IS SURVEYED BY ME AND THE DIMENSIONS OF ALL SIDES OF PLOT AND PLOT AREA AS SHOWN IN PLAN ARE MEASURED BY ENGINEER ON RECORD AND IN ACCORDANCE WITH OWNERSHIP / REVENUE RECORD - ENGINEER IS FULLY RESPONSIBLE FOR LEAVING OPEN SPACE AND MARGIN - THE DEPTH AND POSITION OF EXISTING MUNICIPAL MANHOLE IS VERIFIED BY ME ON SITE AND PREMISES CAN GET DRAINAGE CONNECTION - IT IS CERTIFY THAT ACCORDING TO CGOBR-2017 ALL REQUIREMENTS OF THE BUILDING ARE CHECKED AND NECESSARY ACTIONS ARE TAKEN - IT IS CERTIFY THAT ACCORDING TO THE CLAUSE NO. 4.4.3 OF THE CGOBR-2017 THE STRUCTURE OF THE BUILDING IS DESIGN AS PER THE NORMS OF THE NDMN STANDARDS - DESIGN OF STAIRCASE AND RAILINGS IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 13.1.11 AND 13.1.13 OF CGOBR-2017 - PRESTRESSING RAMP IS PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 13.1.14 OF CGOBR-2017 - DRAINING WATER FACILITY FOR DISABLED PERSONS IS PROVIDED AS PER THE CLAUSE NO. 13.6.2 OF CGOBR-2017 - DRAINAGE FACILITY IS PROVIDED AS PER THE CLAUSE NO. 13.10 OF CGOBR-2017 - SIGNAGES OF THE PARKING PLACE IS TO BE PROVIDED AS PER THE PROVISION OF THE CLAUSE NO. 13.7 OF CGOBR-2017 - ENTRANCE OF THE BUILDING IS PROVIDED AS PER THE CLAUSE NO. 13.1.8 OF CGOBR-2017 - THE PAVING OF BUILDING UNIFORM PLOT AS PER THE PROVISION OF THE CLAUSE NO. 13.1.13 OF CGOBR-2017 - THE STRUCTURAL DESIGN OF THE BUILDING IS AS PER THE NORMS OF THE SPECIFIED IN THE NDMN STANDARD - THE NECESSARY ACTION SHALL BE TAKEN FOR THE STRUCTURAL SAFETY DURING CONSTRUCTION - RAIN WATER STORAGE TANK AND RAIN WATER HARVESTING SYSTEM SHALL BE PROVIDED AS PER CLAUSE NO. 17.2 OF CGOBR-2017 - COMMUNITY BENEFICIARY AS PER THE PROVISION OF THE CLAUSE NO. 17.2.4 & 17.2.5 OF CGOBR-2017 - TREE PLANTATION IS PROVIDED AS PER THE CLAUSE NO. 17.4 OF CGOBR-2017 - MAINTENANCE AND UPGRADATION OF BUILDING IS AS PER CHAPTER NO. 19 OF CGOBR-2017 - ROOF TOP SOLAR ENERGY INSTALLATION & GENERATION SHALL BE PROVIDED AS PER CLAUSE NO. 17.5.1 OF CGOBR-2017	
For, RUDRA BUILDCON <i>(Signature)</i> Partner	
OWNER	
<i>(Signature)</i> DINKAR BUILDCON A.M.C. DEV. LIC. NO. 116740523 Partner, Divyansh G. Patel 12, Suncity Bunglows, Nikel, A'sad	<i>(Signature)</i> Rohit B. Prajapati COW-1 LIC. NO. 0489716121R1 3, Sadguru Homes, Nandani Nikel Ahmedabad-382350.
DEVELOPER	C.O.W.
<i>(Signature)</i> Rohit B. Prajapati Eng. Lic. No. 0782100221R1 3, Sadguru Homes, Nandani Nikel. Ahmedabad-382350.	<i>(Signature)</i> Jayesh D. Desai S.D.-1 Lic. No. 0349200221R1 87, Art Tenament Ghatlodiya, A'sad-61.
ENGINEER	STR. ENGINEER

The permission is valid only Till the DP/TPS remains unaltered and further along the period shall stand revocable as soon there is change in DP/TPS with reference to the land under reference.

Final Plan boundary and allotment of final plot is Subject to Verification by Town Planning Officer

BLOCK - C
ELE. S.S.

... का निर्माण तथा संबंधी सुविधाओं की पूर्ति का प्रस्ताव है,
सा(२०१७)३३५/२०-१४-९६ के अन्तर्गत आशुपूर गाँव में,
राजेश कोटि शर्मा द्वारा उपरोक्त स्थान पर विद्यमान एक फ्लैट को
नया बनायी जाये।

For, RUDRA BUILDCON <i>[Signature]</i> Partner		OWNER
<i>[Signature]</i> DINKAR BUILDCON AMC.DEV.LIC.NO.117240923 Partner, Dnyang G. Patel 12, Suncity Bungalows, Nikol, A'bad	<i>[Signature]</i> Rohit B. Prajapaty COW-1 LIC No. 0489170121R1 3, Sadguru Homes, Nava Nikol Ahmedabad-382350.	C.O.W.
<i>[Signature]</i> Rohit B. Prajapaty Eng. Lic. No. 0782100221R1 3, Sadguru Homes, Nava Nikol Ahmedabad-382350.	<i>[Signature]</i> Jayesh D. Desai S.D.-1 Lic No. 0349200221R1 87, Arli Tenament, Ghatodiya, A'bad-61.	STR. ENGINEER
ENGINEER		





Ahmedabad Municipal Corporation

ENAGAR APPLICATION NO :- 001BDF192000R7
ODPS Application ID - ODPS2019002212
Case No :- BLNTUE2019020/CGDCRVA/3837/RO/MI

This Development permission has been granted only for the ODPS (Online Development Permission System). ENAGAR approved reference case vide Notification No. PHC/21/120010/1841, dated 20/06/2019 of Urban Development and Urban Housing Department, Government Of Gujarat and directions issued by competent authority from time to time, under provision of Comprehensive General Development Control Regulations-2017

Plan approved as per terms and condition mentioned in the commencement Certificate (Rajachitti)

Raja Chitti Number :- **03875101920/AS3837/RO/MI**
 Date: **03-07-2020**










T.D. Sub/Inspector (B.P.S.P.) T.D. Inspector (B.P.S.P.) Asst. T.D.O. (B.P.S.P.)

AUTHORITY



CARPET AREA (IN SQ MT)		TENAMENT & FLOOR AREA TABLE - (IN SQ MT)			
BLOCK	TOTAL F.A	BLOCK	USE	EQ TENA	TOTAL F.A
A	1280.91	A	IN SHED	21	1280.91
B	1537.80	B	IN SHED	24	1537.80
TOTAL	2818.71	TOTAL		45	2818.71



Final Plan boundary and
allotment of final plot is
Subject to Variation by
Town Planning Officer

BDSP, TDO, AMC

2. 'हरी विस्तार' नाम वाले मुद्रापात्रों का प्रसारण एवं वितरण.
(२२/०८२०१०/६३१११) टी-१६-११-१० का यह अनुसार आंकड़ों की
जवाबों में भी उल्लेख 'मुद्रा टी आर' के आंकड़ों की तथ्य विधियों द्वारा किंतु
कभी मुद्रा की शर्तों. —

AUTHORITY

ENGINEER