

NOTES:

1. That C.C. for sale building shall be controlled in a phasewise manner as decided by CEO (SRA) in proportion with the actual work of rehabilitation component as per Circular No. 98 & 104.
2. That no occupation permission of any of the sale wing/sale building/sale area shall be considered until Occupation Certificate for equivalent Rehabilitation area is granted.
3. That CEO (SRA) reserves right to add or amend or delete some of the above or all the above mentioned conditions if required, during execution of Slum Rehabilitation Scheme.


29/9/12
Executive Engineer - I
Slum Rehabilitation Authority

NOTES

- (1) The work should not be started unless objections _____ are complied with.
- (2) A certified set of latest approved plans shall be displayed on site at the time of commencement of the work and during the progress of the construction work.
- (3) Temporary permission on payment of deposit should be obtained for any shed to house and store for constructional purposes, Residence of workmen shall not be allowed on site. The temporary structures for storing constructional materials shall be demolished before submission of building completion certificate and a certificate signed by Architect submitted alongwith the building completion certificate.
- (4) Temporary sanitary accommodation on full flushing system with necessary drainage arrangement should be provided on site for workers, before starting the work.
- (5) Water connection for constructional purposes will not be given until the hoarding is constructed and application is made to the Ward Officer of M.C.G.M. with the required deposit for the construction of carriage entrance, over the road side drain.
- (6) The owners shall intimate the Hydraulic Engineer of M.C.G.M. or his representative in wards of M.C.G.M. atleast 15 days prior to the date of which the proposed construction work is taken in hand that the water existing in the compound will be utilised for their construction works and they will not use any Municipal Water for construction purposes. Failing this, it will be presumed that Municipal tap water has been consumed on the construction works and bills preferred against them accordingly.
- (7) The hoarding or screen wall for supporting the depots of building materials shall be constructed before starting any work even though no materials may be expected to be stabled in front of the property. The scaffoldings, bricks, metal, sand, preps, debris etc. should not be deposited over footpaths or public street by the owner/architect/their contractors, etc. without obtaining prior permission from the Ward Officer of the area.
- (8) The work should not be started unless the compliance of abovesaid conditions is approved by this department.
- (9) No work should be started unless the structural design is submitted from LSE.
- (10) The work above plinth should not be started before the same is shown to this office Sub-Engineer (SRA) concerned and acknowledgement obtained from him regarding correctness of the open spaces dimension.
- (11) The application for sewer street connections, if necessary, should be made simultaneously with commencement of the work as the Municipal Corporation of Greater Mumbai will require time to consider alternative site to avoid the excavation of the road and footpath.
- (12) All the terms and conditions of the approved layout/sub-division/Amalgamation under No. _____ should be adhered to and complied with.
- (13) No building/Drainage Completion Certificate will be accepted and water connection granted (except for the construction purposes) unless road is constructed to the satisfaction of the concerned Ex. Engineer of M.C.G.M. and as per the terms and conditions for sanction to the layout.
- (14) Recreation ground or amenity open space should be developed before submission of building Completion Certificate.
- (15) The access road to the full width shall be constructed in water bound macadam before commencing work and should be complete to the satisfaction of concerned. Ex-Engineer of M.C.G.M. including asphaltting, lighting and drainage before submission of the building Completion Certificate.
- (16) Flow of water through adjoining holding or culvert, if any should be maintained unobstructed.
- (17) The surrounding open spaces around the building should be consolidated in concrete having broken glass pieces at the rate of 0.125 cubic metres per 10 Sq.Mtrs below pavement.

- (18) The compound wall or fencing should be constructed clear of the road widening line with foundation below level of the bottom of road side drain without obstructing flow of rain water from adjoining holding before starting the work to prove the owner's holding.
- (19) No work should be started unless the existing structures or proposed to be demolished are demolished.
- (20) If it is proposed to demolish the existing structures by negotiations with the tenants, under the circumstances, the work as per approved plans should not be taken up in hand unless the Chief Engineer [SRA] is satisfied with the following :
 - (i) Specific plans in respect of evicting or rehousing the existing tenants on your plot stating their number and the area in occupation of each.
 - (ii) Specifically signed agreement between you and the existing tenants that they are willing to avail for the alternative accommodation in the proposed structure.
 - (iii) Plans showing the phase programme of construction has to be duly approved by this office before starting the work so as not to contravene at any stage of construction, the Development Control Rules regarding open spaces, light and ventilation of existing structure.
- (21) In case of additional floor no work should be started during monsoon which will give rise to water leakage and consequent nuisance to the tenants staying on the floor below.
- (22) The bottom of the over head storage work above the finished level of the terrace shall not be more than 1 metre.
- (23) The work should not be started above first floor level unless the No Objection Certificate from the Civil Aviation Authorities, where necessary, is obtained.
- (24) It is to be understood that the foundations must be excavated down to hard soil.
- (25) The positions of the nahanis and other appurtenances in the building should be so arranged as not to necessitate the laying of drains inside the building.
- (26) No new well, tank, pond, cistern or fountain shall be dug or constructed without the previous permission in writing from the Chief Executive Officer of Slum Rehabilitation Authority.
- (27) All gully traps and open channel shall be provided with right fitting mosquito proof covers as per relevant I. S. specifications.
- (28) No broken bottle should be fixed over boundary walls. The prohibition refers only to broken bottles & not to the use of plain glass for coping over compound wall.
- (29) If the proposed addition is intended to be carried out on old foundations and structures, you will do so at your own risk.


 Executive Engineers, (S.R.A.)