



MUNICIPAL CORPORATION OF GREATER MUMBAI

Intimation of Disapproval under Section 346 of the Mumbai Municipal Corporation Act, as amended up to date.

No. CHE/ES/5144/S/337(NEW)

MEMORANDUM

Municipal Office,
Mumbai

To,

M/S. SUDHANSHU INFRASTRUCTURES PVT. LTD.

B 24, 24 A, ANIRAJ TOWER, OPP. KAKA PETROL PUMP, L.B.S. MARG, BHANDUP (W),
MUMBAI – 400 078

With reference to your Notice 337 (New) , letter No. 8311 dated. 22/10/2018 and the plans, Sections Specifications and description and further particulars and details of your buildings at PROPOSED REDEVELOPMENT OF EXISTING BUILDING ON PLOT BEARING C.T.S. NO. 716 & 719 OF VILLAGE KANJUR, BHANDUP (EAST) AT DATAR COLONY, VEER SAVARKAR MARG., CTS NO.716 & 719 furnished to me under your letter, dated 22/10/2018. I have to inform you that, I cannot approve of the building or work proposed to be erected or executed, and I therefore hereby formally intimate to you, under Section 346 of the Mumbai Municipal Corporation Act as amended up to-date, my disapproval by reasons thereof :-

A: CONDITIONS TO BE COMPILED WITH BEFORE STARTING THE WORK.

- 1 That the Janata Insurance Policy shall not be submitted.
- 2 That the requisitions of clause 45 & 46 of DCR 91 shall not be complied with and records of quality of work, verification report, etc. shall not be maintained on site till completion of entire work
- 3 That the bore well shall not be constructed in consultation with H. E.
- 4 That the work shall not be carried out between 6.00 a.m. to 10.00 p.m. in accordance with Rule 5A (3) of the Noise Pollution(Regulation & Control) Rules, 2000 and the provision of notification issued by Ministry of Environment and Forest department from time to time shall not be duly observed.
- 5 That the Board shall not be displayed showing details of proposed work, name of owner, developer,
- 6 That the Pre-requisites as per Ease Of Doing Business circular shall not be submitted before applying for Plinth C.C.
- 7 NOTE: This Intimation of Disapproval is PROVISIONAL and upto plinth and issued on the basis of terms and conditions contained in the registered Undertaking cum Indemnity by the owner dated 03/11/2018 annexed to this IOD

- () That proper gutters and down pipes are not intended to be put to prevent water dropping from the leaves of the roof on the public street.
- () That the drainage work generally is not intended to be executed in accordance with the Municipal requirements.

Subject to your so modifying your intention as to obviate the before mentioned objections and meet by requirements, but not otherwise you will be at liberty to proceed with the said building or work at anytime before the _____ day of _____ but not so as to contrivance any of the provision of the said Act, as amended as aforesaid or any rule, regulations or bye-law made under that Act at the time In force.

Your attention is drawn to the Special Instructions and Note accompanying this Intimation of Disapproval.

**Executive Engineer, Building Proposals,
Zone, Wards.**

SPECIAL INSTRUCTIONS

1. THIS INTIMATION GIVES NO RIGHT TO BUILD UPON GROUND WHICH IS NOT YOUR PROPERTY.

2. Under Section 68 of the Bombay Municipal Corporation Act, as amended, the Municipal Commissioner for Greater Mumbai has empowered the City Engineer to exercise, perform and discharge the powers, duties and functions conferred and imposed upon and vested in the Commissioner by Section 346 of the said Act.

3. Under Byelaw, No. 8 of the Commissioner has fixed the following levels :-

"Every person who shall erect as new domestic building shall cause the same to be built so that every part of the plinth shall be-

- a) Not less than, 2 feet (60 cms.) above the center of the adjoining street at the nearest point at which the drain from such building can be connected with the sewer than existing or thereafter to be- laid in such street
- b) Not less than 2 feet (60 cms.) Above every portion of the ground within 5 feet (160 cms.)-of such building.
- c) Not less than 92 ft. ([!TownHall]) above Town Hall Datum.

4. Your attention is invited to the provision of Section 152 of the Act whereby the person liable to pay property taxes is required to give notice of erection of a new building or occupation of building which has been vacant, to the Commissioner, within fifteen days of the completion or of the occupation whichever first occurs. Thus compliance with this provision is punishable under Section 471 of the Act irrespective of the fact that the valuation of the premises will be liable to be revised under Section 167 of the Act, from the earliest possible date in the current year in which the completion on occupation is detected by the Assessor and Collector's Department.

5. Your attention is further drawn to the provision of Section 353-A about the necessity of submitting occupation certificate with a view to enable the Municipal Commissioner for Greater Mumbai to inspect your premises and to grant a permission before occupation and to levy penalty for non-compliance under Section 471 if necessary.


6. Proposed date of commencement of work should be communicated as per requirements of Section 347 (1) (aa) of the Bombay Municipal Corporation Act.

7. One more copy of the block plan should be submitted for the Collector, Mumbai Suburbs District.

8. Necessary permission for Non-agricultural use of the land shall be obtained from the Collector Mumbai Suburban District

before the work is started. The Non-agricultural assessment shall be paid at the site that may be fixed by the Collector, under the Land Revenue Code and Rules there under.

Attention is drawn to the notes Accompanying this Intimation of Disapproval.



No. EB/CE/

/BS

/A/

NOTES

- 1) The work should not be started unless objections are complied with
- 2) A certified set of latest approved plans shall be displayed on site at the time of commencement the work and during the progress of the construction work.
- 3) Temporary permission on payment of deposit should be obtained any shed to house and store for construction purpose, Residence of workmen shall not be allowed on site. The temporary structures for storing constructional material shall be demolished before submission of building completion certificate and certificate signed by Architect submitted along with the building completion certificate.
- 4) Temporary sanitary accommodation on full flushing system with necessary drainage arrangement should be provided on site workers, before starting the work.
- 5) Water connection for constructional purpose will not be given until the hoarding is constructed and application made to the Ward Officer with the required deposit for the construction of carriage entrance, over the road side drain.
- 6) The owners shall intimate the Hydraulic Engineer or his representative in Wards atleast 15 days prior to the date of which the proposed construction work is taken in hand that the water existing in the compound will be utilised for their construction works and they will not use any Municipal Water for construction purposes. Failing this, it will be presume that Municipal tap water has been consumed on the construction works and bills preferred against them accordingly.
- 7) The hoarding or screen wall for supporting the depots of building materials shall be constructed before starting any work even though no materials may be expected to be stabled in front of the property. The scaffoldings, bricks metal, sand preps debris, etc. should not be deposited over footpaths or public street by the owner/ architect /their contractors, etc without obtaining prior permission from the Ward Officer of the area.
- 8) The work should not be started unless the manner in obviating all the objection is approved by this department.
- 9) No work should be started unless the structural design is approved.
- 10) The work above plinth should not be started before the same is shown to this office Sub-Engineer concerned and acknowledgement obtained from him regarding correctness of the open spaces & dimension.
- 11) The application for sewer street connections, if necessary, should be made simultaneously with commencement of the work as the Municipal Corporation will require time to consider alternative site to avoid the excavation of the road an footpath.

- 12) All the terms and condition of the approved layout /sub-division under No. of should be adhered to and complied with.
- 13) No Building /Drainage Completion Certificate will be accepted non water connection granted (except for the construction purpose) unless road is constructed to the satisfaction of the Municipal Commissioner as per the provision of Section 345 of the Bombay Municipal Corporation Act and as per the terms and conditions for sanction to the layout.
- 14) Recreation ground or amenity open space should be developed before submission of Building Completion Certificate.
- 15) The access road to the full width shall be constructed in water bound macadam before commencing work and should be complete to the satisfaction of Municipal Commissioner including asphaltting lighting and drainage before submission of the Building Completion Certificate.
- 16) Flow of water through adjoining holding or culvert, if any should be maintained unobstructed.
- 17) The surrounding open spaces around the building should be consolidated in Concrete having broke glass pieces at the rate of 12.5 cubic meters per 10 sq. meters below payment.
- 18) The compound wall or fencing should be constructed clear of the road widening line with foundation below level of bottom of road side drain without obstructing flow of rain water from adjoining holding before starting the work to prove the owner's holding.
- 19) No work should be started unless the existing structures proposed to be demolished are demolished.
- 20) The Intimation of Disapproval is given exclusively for the purpose of enabling you to proceeds further with the arrangements of obtaining No Objection Certificate from the Housing Commissioner under Section 13 (h) (H) of the Rent Act and in the event f your proceeding with the work either without an intimation about commencing the work under Section 347(1) (aa) or your starting the work without removing the structures proposed to be removed the act shall be taken as a severe breach of the conditions under which this Intimation of Disapproval is issued and the sanctioned will be revoked and the commencement certificate granted under Section 45 of the Maharashtra Regional and Town Planning Act 1966, (12 of the Town Planning Act), will be with drawn.
- 21) If it is proposed to demolish the existing structures be negotiations with the tenant, under the circumstances, the work as per approved plans should not be taken up in hand unless the City Engineer is satisfied with the following:-
 - i. Specific plans in respect of evicting or rehousing the existing tenants on hour stating their number and the areas in occupation of each.
 - ii. Specifically signed agreement between you and the existing tenants that they are willing to avail or the alternative accommodation in the proposed structure at standard rent.
 - iii. Plans showing the phased programme of constructions has to be duly approved by this office before starting the work so as not to contravene at any stage of construction, the Development control Rules regarding open spaces, light and ventilation of existing structure.

- 22) In case of extension to existing building, blocking of existing windows of rooms deriving light and its from other sides should be done first starting the work.
- 23) In case of additional floor no work should be start or during monsoon which will same arise water leakage and consequent nuisance to the tenants staying on the floor below.
- 24) The bottom of the over head storage work above the finished level of the terrace shall not be less than 1.20 Mt.and not more than 1.80 mt.
- 25) The work should not be started above first floor level unless the No Objection Certificate from the Civil Aviation Authorities, where necessary is obtained.
- 26) It is to be understood that the foundations must be excavated down to hard soil.
- 27) The positions of the nahanis and other appurtenances in the building should be so arranged as not to necessitate the laying of drains inside the building.
- 28) The water arrangement nut be carried out in strict accordance with the Municipal requirements.
- 29) No new well, tank, pond, cistern or fountain shall be dug or constructed without the previous permission in writing of the Municipal Commissioner for Greater Mumbai, as required in Section 381-A of the Municipal Corporation Act.
- 30) All gully traps and open channel drains shall be provided with right fitting mosquito proof made of wrought iron plates or hinges. The manholes of all cisterns shall be covered with a properly fitting mosquito proof hinged cast iron cap over in one piece, with locking arrangement provided with a bolt and huge screwed on highly serving the purpose of lock and the warning pipes of the rabbet pretested with screw or dome shape pieces (like a garden mari rose) with copper pipes with perfections each not exceeding 1.5 mm in diameter. The cistern shall be made easily, safely and permanently accessible be providing a firmly fixed iron ladder, the upper ends of the ladder should be earmarked and extended 40 cms above the top where they are to be fixed as its lower ends in cement concrete blocks.
- 31) No broken bottles should be fixed over boundary walls. This prohibition refers only to broken bottles to not to the use of plane glass for coping over compound wall.
- 32) a Louvres should be provided as required by Bye0law No. 5 (b)
b Lintels or Arches should be provided over Door and Windows opening
c The drains should be laid as require under Section 234-1(a)
d The inspection chamber should be plastered inside and outside.
- 33) If the proposed additional is intended to be carried out on old foundations and structures, you will do so as your own risk.


**Executive Engineer, Building Proposals
Zones wards.**

CHE/ES/5144/S/337(NEW)


- Copy To :-
1. RAMJIBHAI POPATBHAI ASUNDARIA
236, Avior Bldg., Nirmal Galaxy, Near Deepmandir Cinema, L.B.S Marg, Mulund (W), Mumbai 400080
 2. Asst. Commissioner S Ward.
 3. A.E.W.W. S Ward,
 4. Dy.A & C. Eastern Suburb
 5. Chief Officer, M.B.R. & R. Board S Ward .
 6. Designated Officer, Asstt. Engg. (B. & F.) S Ward ,
 7. The Collector of Mumbai




Name : AVINASH GORAKSH
TAMBEWAGH
Designation : Executive
Engineer
Organization : Personal \\
Date : 10-Dec-2018 10: 38:26




GROUND FLOOR
SCALE : 1:100




SECTION THROUGH
UNDER GROUND TANK
SCALE : 1: 100



SECTION THROUGH
COMPOUND WALL
SCALE : 1: 50



LOCATION PLAN
SCALE : 1: 4000



BLOCK PLAN
SCALE : 1:100

CONTENTS OF SHEET	CERTIFICATE OF AREA
- GROUND FLOOR PLAN - SECT. THRO COMP. WALL & U.G. TANK - BLOCK & LOCATION PLAN - SECTION - 'A'- 'A' - SECTION - 'B'- 'B' - SECTION - 'C'- 'C' - SECTION - 'D'- 'D'	Certified that I have surveyed the plot under reference on 22-10-2018 and that the dimensions of the sides, etc. of the plot stated on the plan are as measured on site and the area so worked out and tallies with the area stated in the document of ownership / town planning scheme record.
NAME & SIGN. OF THE OWNER	DESCRIPTION OF PROPOSAL
Abhayjeet Sakalnarayan Dubey M/S. SUDHANSHU INFRASTRUCTURES PVT. LTD. B-24/24A, ANIRAJ TOWER CHS LTD., L.B.S. MARG, BHANDUP (W), MUMBAI-400 078	PROPOSED BUILDING ON PLOT BEARING C.T.S. NO. 716 & 719 OF VILLAGE KANJUR, BHANDUP (E) AT DATAR COLONY, VEER SAVARKAR MARG.

STAMP & DATE OF APPROVAL OF PLAN

APPROVED SUBJECT TO THE CONDITIONS MENTIONED
IN THIS OFFICE LETTER AUTO DCR NO. CHE/ES/5144/S/337(NEW)

E.E.(B.P.) E.S.-II

S.E.(B.P.) S&T/E

A.E.(B.P.) S & T

I.	AREA STATEMENT	AREA IN SQMT
1.	GROSS AREA OF PLOT	8 3 6 . 2 0
	a) Area of Reservation in plot	N I L
	b) Area of Road Set back	N I L
	c) Area of D.P. Road	N I L
2.	DEDUCTIONS FOR.	
	(A) For Reservation/Road Area	
	(a) Road set-back area to be handed over (100%) (Regulation No.16)	- - -
	(b) Proposed D.P. road to be handed over (100%) (Regulation No.16)	- - -
	(c) Reservation area (plot) to be handed over (Regulation No.17)	- - -
	(B) For Amenity Area	
	(a) Area of amenity plot/plots to be handed over as per DCR 14(A)	N I L
	(b) Area of amenity plot/plots to be handed over as per DCR 14(B)	N I L
	(c) Area of amenity plot/plots to be handed over as per DCR 15	N I L
	(d) Area of amenity plot/plots to be handed over as per DCR 35	N I L
	(C) Deductions for Existing Built up area to be retained if any	
	(a) Land component of Existing BUA as per regulation	N I L
3.	TOTAL DEDUCTIONS:[2(A)+2(B)+2(C)]	N I L
4.	BALANCE AREA OF PLOT (1 minus 3)	8 3 6 . 2 0
5.	PLOT AREA UNDER DEVELOPMENT	8 3 6 . 2 0
6.	ZONAL (BASIC) FSI (1 or 1.33)	0 N E
7.	PERMISSIBLE BUILT UP AREA AS PER ZONAL (BASIC) FSI (5X6) (In case of mill land permissible Built up Area shall be as per 4 of Regulation 30(A)	8 3 6 . 2 0
8.	BUILT UP AREA EQUAL TO AREA OF LAND HANDED OVER AS PER 3(a) OF REGULATION30(A)	N I L
9.	BUILT UP AREA IN LIEU OF COST OF CONSTRUCTION OF BUILT UP AMENITY TO BE HANDED OVER	N I L
10.	BUILT UP AREA DUE TO "ADDITIONAL FSI ON PAYMENT OF PREMIUM " AS PER TABLE NO.12 OF REGULATION NO 30(A) SUBJECT TO REGULATION NO.30(A)3	N I L
11.	EXISTING B.U.A TO BE PROTECTED U/NO. CE/4024/B.P.E.S./AN DATED 24/02/1983 (83.60) U/NO. CE/2915/B.P.E.S./AN DATED 15/06/2010(111.48) a)EXISTING MEMBERS F.S.I.(29X10=290 SQ.MT.) b)0.70 TDR (PERMISSIBLE=836.20X0.70=585.34 SQ.MT.) (585.34-(195.08-270.00)=120.26	N I L N I L N I L N I L
12.	PERMISSIBLE BUILT UP AREA (7+8+9+10+11)	8 3 6 . 2 0
13.	PROPOSED BUILT UP AREA	N I L
14.	TDR GENERATED IF ANY AS PER REGULATION 30 (A)	N I L
15.	FUNGIBLE COMPENSATORY AREA AS PER REGULATION NO.31)3) a) i) Permissible Fungible Compensatory area for rehab component without charging premium ii) Fungible Compensatory area for availed for Rehab Component without charging premium b) i) Permissible Fungible Compensatory area by charging premium ii) Fungible Compensatory area availed on payment of premium	N I L N I L N I L N I L N I L N I L
16.	TOTAL BUILT UP AREA PROPOSED INCLUDING FUNGIBLE COMPENSATORY AREA[13+15(a)(i)+15(b)(ii)]	N I L
17.	FSI CONSUMED ON NET PLOT [13/4]	N I L
(ii)	OTHER REQUIREMENTS	
	(A) RESERVATION/DESIGNATION	
	a) Name of Reservation	N I L
	b) Area of Reservation affecting the plot	N I L
	c) Area of Reservation land to be handed/handed over as per regulation No.17	N I L
	d) Built up area of Amenity to be handed over as per regulation No.17	N I L
	e) Area/Built up Area of Designation	N I L
	(B) RESERVATION/DESIGNATION	
	(i) 14(A)	N I L
	(ii) 14(B)	N I L
	(iii) 15	N I L
	(C) Requirement of Recreational Open Space in Layout/Plot as per Regulation No.27	N I L
	(D) Tenement Statement	
	(i) Proposed Built up Area (13above)	N I L
	(ii) Less deduction of Non-residential area (Shop etc)	N I L
	(iii) Area available for tenements[(i) minus (ii)]	N I L
	(iv) Tenement permissible (Density of tenement/hectare)	N I L
	(v) Total No of Tenement Proposed on the plot	N I L
	(E) Parking Statement	
	(i) Parking Required by regulations for:-	- - -
	Car	- - -
	Scooter/Motor cycle	- - -
	Outsider (visitors)	- - -
	(ii) Covered garage permissible	- - -
	(iii) Covered garage proposed	- - -
	Car	- - -
	Scooter/Motor cycle	- - -
	Outsider (visitors)	- - -
	(iv) Total parking provided	- - -
	(D) Transport Vehicles Parking	
	(i) Space for transport vehicles parking required by Regulations	- - -
	(ii) Total No. of transport vehicles parking spaces provided	- - -

SCALE	NAME & SIGN OF ARCHITECT
AS SPECIFIED	
NORTH	
	R. P. ASUNDARIA ARCHITECT 236, 2ND FLOOR, AVIOR, NIRMAL GALAXY, NEAR DEEP MANDIR CINEMA, L.B.S. MARG, MULUND (WEST), MUMBAI - 400 080 Tel : 25679979