

Staircase Details
Width - 1.22
Riser - 0.165
Tread - 0.27



BLOCK-B
ಹೊಸಕೋಟೆ ಯೋಜನಾ ಪ್ರಾಧಿಕಾರ
ಅಭಿವೃದ್ಧಿ ನಕ್ಷೆಗೆ ಮಂಜೂರಾತಿ ಆದೇಶದಂತೆ
ಕೆ.ಟಿ.ಸಿ.ಪಿ. ಆಕ್ಟ್, 1961 ರ ಕಲಂ 15(1) ರ ಅಡಿಯಲ್ಲಿ ಈ ಕಟ್ಟಡ
ಪ್ಲಾನ್ ಮಂಜೂರು ಮಾಡಲಾಗಿದೆ/ಮಾಡಲಾಗಿದೆ.
ಮಂಜೂರಾತಿ ಸಂಖ್ಯೆ: ಹೊಪ್ರಾ/ಬಿ.ಎಲ್.ಡಿ.ಸಿ/ಕಟ್ಟಡ/0093/23
ದಿನಾಂಕ / ಕಛೇರಿ ಟಿಪ್ಪಣಿಯ ಮೇರೆಗೆ ಈ ನಕ್ಷೆಗೆ ಮಂಜೂರಾತಿ ಆದೇಶದಂತೆ ಕಾಲಾವಧಿ.

SANCTIONING AUTHORITY

ASSISTANT DIRECTOR OF TOWN & COUNTRY PLANNING.

DEPUTY DIRECTOR OF TOWN & COUNTRY PLANNING (Cle)

JOINT DIRECTOR OF TOWN & COUNTRY PLANNING & MEMBER SECRETARY

HOSKOTE PLANNING AUTHORITY, HOSKOTE.

INDEX	
SITE BOUNDARY	
SET BACK LINE	
PLINTH LINE	
Solar photo voltaic lights	solar light
FOOT KHARAB AREA	

Solar Water Heater - 500 LPCD porvided

SCHEDULE OF OPENINGS		
TYPE	DESCRIPTION	SIZE
D	DOOR	1.00 x 2.10
D1	DOOR	0.90 x 2.10
D2	DOOR	0.75 x 2.10
DD	DOOR	1.20 x 2.10
W1	WINDOWS	1.50 x 1.20
W2	WINDOWS	1.20 x 1.20
W3	WINDOWS	0.90 x 1.20
V	VENTILATAR	0.76 x 0.90
FD	FOLDING DOOR	2.20 x 2.10

CONVERSION ORDER NUMBERS					
Sl No	Village Name	Sy No	Total Extent Acres Guntas	Deposit Fee Rs.Ps	Conversion Order Number & Date
01	KALUVANAHALLI	26/1	1 10.50	1.0	UPN CAD/NA/HSK/ 0 Dtd: 00-04-2022
Total Area			1 10.50	1.0	

SINGLE SITE LAND USE ANALYSIS			
S.No.	DESCRIPTION	AREA in Sq.m as per Plan	% as Per Plan
1	Residential Area	7435.99	100.00
	TOTAL	7435.99	100.00

STABILITY CERTIFICATE

This is to certify that, this Apartment building is reinforced concrete framed structure with columns, beam and slabs system, and is comprising with bareas of Indian standards norms. The structure is designed for Stilt Floor Ground floor and Three upper floors in accordance with IS 456(Gravity load only) and with consideration of safe soil bearing capacity.

Y. BHASKAR
BCC/BL-3.6/SE-0315/2019-20



KEY MAP
NTS

ALL DIMENSIONS ARE IN METERS

BLOCK-A (GROUND FLOOR)

S.No	NAME	TOTAL AREA IN SQM	No.OF UNITS PER FLOOR	UNIT Nos.
01	2BHK	> 50 SQ.M	06 Nos	3,6,7,11,18,17
02	3BHK	> 50 SQ.M	12 Nos	1,2,4,5,8,9,10,12 13,14,16,18
TOTAL			18 Nos	

No. OF UNITS IN GROUND FLOOR BLOCK-A 18 Nos.

BLOCK-A (TYPICAL FLOOR 3 FLOORS (FIRST, SECOND & THIRD)

S.No	NAME	TOTAL AREA IN SQM	No.OF UNITS PER FLOOR	UNIT Nos.
01	2BHK	> 50 SQ.M	07 Nos.	3,6,9,13,17,19,21
02	3BHK	> 50 SQ.M	15 Nos	1,2,4,5,8,7,10,11,12, 14,15,16,18,20,22
TOTAL			22 Nos	

TYPICAL 3 FLOORS(1st,2nd & 3rd Floor)BLOCK-A=22UNITS x 3 Floors)= 66 UNITS
TOTAL No. OF UNITS IN BLOCK -A (G+3 FLOORS) = 18+66 = 84 UNITS

BLOCK-B (TYPICAL FLOOR(G+3 FLOORS)

S.No	NAME	TOTAL AREA IN SQM	No.OF UNITS PER FLOOR	UNIT Nos.
01	2BHK	> 50 SQ.M	03 Nos	3,7,9
02	3BHK	> 50 SQ.M	07 Nos	1,2,4,5,6,8,10
TOTAL			10 Nos.	

TYPICAL 4 FLOORS(GROUND+3 Floors)=10 UNITS x 4 Floors)
TOTAL No. OF UNITS IN BLOCK-B = 40 UNITS
TOTAL No.of UNITS (BLOCK - A & B)
BLOCK-A = 84 UNITS
BLOCK-B = 40 UNITS
TOTAL = 124 UNITS

AREA STATEMENTS

TOTAL SITE AREA AS PER 39 SURVEY NUMBERS (7435.99 Sqm)
POOT KHARAB AREA = 00.17 SQ.M (EXCLUDED)
NET SITE AREA = TOTAL PLOT AREA
NET SITE AREA = 7435.99 SQ.M

BUILT UP AREA STATEMENT (IN SQM)

SL NO.	FLOOR	GROSS BUILT UP AREA	DEDUCTIONS (Area in Sqm)				NET BUILT UP AREA	FAR Permissible	FAR Consumed	Remarks
			STAIRS	LIFT	DUCT	TOTAL				
BLOCK-A										
1	Stilt	2566.82	41.63	9.86	2.16	53.65	2513.17		33.82	
2	Ground	2566.82	38.36	22.80	6.76		2539.46	18	33.54	
3	First	2566.82	44.78	22.80	6.76		2539.46	18	33.54	
4	Second	2566.82	44.78	22.80	6.76		2539.46	18	33.54	
5	Third	2566.82	44.78	22.80	6.76		2539.46	18	33.54	
6	Terrace	00.00	00.00	00.00	00.00	00.00	00.00		00.00	
Grand Total		15400.92	214.33	100.26	29.20	344.79	15056.13	90	198.98	
			NET BUILT UP AREA				15056.13			
			GROUND COVERAGE AREA				2513.17			
BLOCK-B										
1	Stilt	1254.96	7.32	9.86	2.16	19.34	1235.62		16.32	
2	Ground	1253.36	38.36	9.86	2.16		1253.36	10	16.54	
3	First	1253.36	38.36	9.86	2.16		1253.36	10	16.54	
4	Second	1253.36	38.36	9.86	2.16		1253.36	10	16.54	
5	Third	1253.36	38.36	9.86	2.16		1253.36	10	16.54	
6	Terrace	29.27	29.27			29.27	29.27	0.00		
Grand Total		7297.67	190.03	49.30	10.80	48.61	7258.33	50	82.48	
			NET BUILT UP AREA				7258.33			
			NET FAR AREA				6035.47			
			GROUND COVERAGE AREA				1253.36			
COMBINED AREA & STATEMENT (BLOCK-A & BLOCK-B)										
1	Stilt	3820.42	48.95	19.72	4.32	72.99	3747.79		49.54	
2	Ground	3820.18	76.72	32.66	8.92		3792.82	28	50.08	
3	1st	3819.18	83.14	32.66	8.92		3792.82	28	50.08	
4	2nd	3819.18	83.14	32.66	8.92		3792.82	28	50.08	
5	3rd	3819.18	83.14	32.66	8.92		3792.82	28	50.08	
6	Terrace	29.27	29.27			29.27	29.27	0.00		
Grand Total		22558.42	404.36	149.56	39.80	102.26	22309.34	140	299.86	
			GROSS BUILT UP AREA				22309.34			
			NET BUILT UP AREA				13293.60			
			NET FAR AREA				13011.25			
			GROUND COVERAGE AREA				3940.47			
							1033.36			

PROPOSED FAR = NET FAR AREA / TOTAL SITE AREA
PROPOSED FAR = 13011.25 / 7435.99 = 1.749
COVERAGE =(GROUND COVERAGE AREA/NET SITE AREA) x 100
COVERAGE = (3940.47 / 7435.99) x 100 = 52.99 %

		AS PER ZONAL REGULATION	AS PER DRAWING
SET BACKS			
ALROUND		5.0 M	5.0 M
		5.0 M	5.0 M
		5.0 M	5.0 M
		5.0 M	5.0 M
Coverage		------	52.99 %
F.A.R		1.75	1.749
No Of Units		------	124 Units
Height of buildings		HIGHT AS PER ZR-19M	14.95 M
Parking	RESIDENTIAL - 124 UNITS) 1 CAR PARKING (2.5 M X 5.0 M) 124 CARS REQUIRED AREA EXCLUDING AREA 5.0 M X 2.5 M = 124 SQ.M = 124 Cars	124 Cars	STILT FLOOR 309.85 SQ.M AREA = 117.4 Cars
	VISITORS PARKING - 10% OF CAR PARKING 124 CARS X 10% = 13 CARS	13 Cars	
	TWO WHEELER PARKING 25% OF TOTAL PARKING 25% x (124 + 13 SQ.M x 137 Nos) = 4270.34 SQ.M		470.94 SQ.M 472.37 Sq.m

OWNERS ASSOCIATION

Shri. RAJAPPA & OTHERS
(RI PRESENTED BY GPA HOLDER)

M/s. SRI JAGATHI PROPERTIES)

PROJECT NAME

PROPOSED RESIDENTIAL APARTMENT IN APPROVED RESIDENTIAL SINGLE SITE VIDE No.HPA/LAYOUT/2023-24,DKZ 21-09-2023 IN KHATA No.465/2601 & E- KHATA No.150300402001100148 Sy.No.26/1 OF GULLEKAYEPURA VILLAGE, ANUGONDANAHALLI HOBLI, HOSKOTE TALUK BANGALORE RURAL DISTRICT.

SUBJECT OF DRAWING — SANCTION PLAN

ORIENTATION	DRAWING No.	
SCALE : 1:150	DN	TYPICAL FLOOR PLAN (1st,2nd & 3rd) TERRACE FLOOR PLAN & ELEVATION DETAILS

ARCHITECT'S SIGNATURE

FOR PWD ARCHITECTS

Regn No. BCC/BL-3.6/A-0315/2019-20