



M/s. REGAL SAMARTH INFRASTRUCTURE Co.

Plot No. 02, First Floor, Regal Civic Centre, Near Axis Bank, Awadhपुरi, BHEL, Bhopal (M.P.) Ph.: (O) 0755-2928835, M : 9302358304

Ref.

Date 09/09/2021

SPECIFICATION OF PROJECT REGAL KALASH PHASE-III

1. Specification of C.C. Road Work

Main Road Width	7.5 meter & 9 meter		
Others Road Width	7.5 meter & 9 meter		
Sub-base	Course	12" thick	Material --- Kopra
Base	Course	8" thick	Material --- GSB
Concrete	Work	5" thick	Grade ----M-30

Specification of Black Top Road

Main Road Width	-N.A.-		
Others Road Width	-N.A.-		
Sub-base	Course	-N.A.-	Material
Base	Course	-N.A.-	Material
Concrete	Work	-N.A.-	Grade

***Note: if other specifications, please insert description

- | | | |
|--------------------------------------|---|--------------------------------|
| 2. Water Storage Tank Capacity | - | 1,00,000 Lt. |
| 3. Water supply line specifications | - | Main line 101 mm-sub line 50mm |
| 4. External electrifications details | - | As per M.P.E.B. Norm's |
| 5. Sewage & Disposal STP details | - | 90 KLD STP 152mm Dia Pipe line |
| 6. Boundary Wall details | - | 6' Heighted |

