

WORK ORDER REPORT

Work Type: Regular

Est. Start Date:

Priority: 0

Required:

Task Status: PLANNING
Assigned To: BHIMANNA_X

Contractor:

Work Order

2153687

Call Back: N

Suite: UTTARAHALL

Task *01²

Page: 1

Budget Head:

Execution Method: DCW DEPT

Task Desc.: dcw estimate

Service Req. No: 4427273

Contact: PUNITH R

Address: KANAKAPURA MAIN ROAD

Landmark:

City/State/Zip: VGP, KAR 560052

Work Phone: Ext:

Problem Code/Desc: LAYOUT - New Layout

Problem Description: Layout: Field Study, Estimation and Execution. Consumer Class: Layout

Component ID: Description:

Dept/Area: 150397-KAGGALIPURA OMU

Task Note Type Notes

stimate prepared for Electrification of Residential Layout in favour of Sri. Punith R, Sy No 124/3, Tharalu

Village, Uttarahally Hobli, Bangaluru south taluk in O&M Unit-2 Kaggalipura, in K-3 Sub division,

Bengaluru-82. (UNDER DCW WORK)

CERTIFICATE Certified that I have inspected the spot and prepared this estimate by using current SR for the most

economical and safest way of executing the work.

SO / AE The 11 KV Extension & Errection of 11 Mtr Spun Pole works estimate are prepared under SELF

EXECUTION WORK. But the 1X250 KVA Transfirmer & Accessories estimate prepared under DCW. The above said work to be carried out by applicant them selves through class-1 Govt electrical contractor

Home Phone:

using BESCOM approved materials. the Approvals from concerned Departments to be Obtained.

COMPATIBLE UNITS:

Capital

ADDRESS

INSTALL

Compatible Unit Description Qty UOM Difficulty
000000000000186 ERECTION OF 250 KVA BEE 5 Star Rated Distribution Transformer, 3 P 1 NO NORMAL

MATERIALS:

Utility Stock Code S.NO Store Item Description Rate Qty.Est UOM Amount(INR) Provided(Y/N) 1 025 321468 Distribution Transformers - 3 520500 NO 520500 Υ

> Phase, 11kV/433V - Stacked Core with Oil as per IS-1180 (Part-1): 2014, OPEN BUSHING TYPE 250kVA, Aluminium Wdg, Star 2 (5

Star)

Sub Total: 520500

LABOR

Submitted by: BHIMANNA_X

Page: 1



WORK ORDER REPORT

S.NO	Stock Code	Item Description	Rate	Qty.Est	UOM	Amount(INR)	Utility Provided(Y/N)	
1	L11KV.6.3	Erection of 200-250 kVA Transformer on Transformer structure.	1727	1	EA	1727	Υ	
			Sub ⁻	Total: 1727				
OTHER RE	QUIREMENTS:	Item [Description	Total: Train		Amoun	t(INR)	=
S_CONT	ING	Contin	gency Charges			10454.9		
ESTBLIS			ishment Charges			449.02	02	
S_TRAN		NULL	onarges			10410		
S_CONT		Contrib	bution towards Employ es & ESI on Total labo %		und	317.077	2	
S_LOCA		(applic	ry Allowance @ ¿.% or cable for areas mention		es	518.1		
S_CGST		CGST				202.059		
S_SGST		SGST	Cost Sub T	otal: 22553.2	2172	202.059		
ATTACHME	-NTS:							
								_
PERMITS:								
Туре		Number	Acquired Date					
Requesto	r Name:				Date:			
COMPLETIO	ON COMMENTS	S:						
Start Date:		Time:	_ Completion Da	ate:		Time:		
		Repair:	_ Compone	ent:				
Follow-up A	Action Required:							

SUMMARY

TASK NO MATERIAI LABOR OTHER REQT TOTAL				
<u></u>	TASK NO	MATERIAL	 OTHER REQT	<u>TOTAL</u>

Submitted by: BHIMANNA_X Page: 2



01	520500	1727	22553.2172	544780.2172	
OVERALL TOTAL	520500	1727	22553.2172	544780.2172	



WORK ORDER REPORT

Work Type: Serv Req

Est. Start Date:

Priority:

Required: 03-SEP-22

Task Status: PLANNING

Assigned To: BHIMANNA_X

Contractor:

2153697

Page: 1

Budget Head:

Execution Method: SELF EXECUTION

Task Desc.: Layout: Field Study, Estimation and Execution. Consumer

Class: Layout

Service Req. No: 4427273

Contact: PUNITH R Call Back: N

Address: KANAKAPURA MAIN ROAD Suite: UTTARAHALL

Landmark:

City/State/Zip: VGP, KAR 560052

Work Phone: Ext: Home Phone:

Problem Code/Desc: LAYOUT - New Layout

Problem Description: Layout: Field Study, Estimation and Execution. Consumer Class: Layout

Component ID: Description:

Dept/Area: 150397-KAGGALIPURA OMU

Task Note Type Notes

CERTIFICATE Certified that I have inspected the spot and prepared this estimate by using current SR for the most

economical and safest way of executing the work.

ADDRESS Estimate Prepared for Electrification of Residential Layout in favour of Sri. Punith R, Sy No 124/3, Tharalu

Village, Uttarahally Hobli, Bangaluru south taluk in O&M Unit-2 Kaggalipura, in K-3 Sub division,

Bengaluru-82. (UNDER SELF EXECUTION WORK)

SO / AE 1. Proposed to extend the 11KV line using 95 Sq.mm UG cable by distance of 100mtrs (LILO System)

from F-03 feeder of Somanahally Muss.

2. Proposed to provide 02 nos of 12 Way LT feeder piller box & 01 no of 8 Way Feeder Piller Box to

provide LT supply to the 25 sites

3. Proposed to provide 120 Sq.mm 3.5core LT UG cable for distance of 0.45 KM (LILO System)

4. Proposed to provide a 02 nos 11mtr spun pole and structure with concerete bed for errection

Transformers & Control of supply.

5. Proposed 05 Nos of LED Fittings with 1.1KV class 4X25sqmm UG Cable, streetlight meter Housing Box,

meter, Automatic switch etc., to illuminate entire layout.

UNDER SELF EXECUTION SCHEME duly collecting the necessary charges.

* No alternative feeder near by the proposed layout.

* No near by Distribution Transformer avaialbale.

* The Proposed residential layout comes under Rural area.

* Proposed LT & HT UG cables are in Loop In Loop Out (LILO) System.

COMPATIBLE UNITS:

Capital

INSTALL

Compatible Unit	Description	Qty UOM	Difficulty
00000000000138	Erection of Pre - Stressed Tubular Spun Pole 11 Mtr Long -500 Kg WL	2 NO	NORMAL
00000000000137	Laying of 11kV, 3 Core, 95 Sqmm XLPE UG Cable Using Conventional L	2 SPAN	NORMAL
000000000000212	Laying of LT UG service main of size 3.5 core 120 Sq. MM 30 M	4 SPAN	NORMAL
00000000000177	LT Feeder Piller box 8 way with cutouts	1 NO	NORMAL

Submitted by: BHIMANNA X



WORK ORDER REPORT

00000000000178 LT Feeder Piller box 12 way with cutouts

2 NO NORMAL

M	IATERIALS	:							
	S.NO	Store	Stock Code	Item Description	Rate	Qty.Est	UOM	Amount(INR)	Utility Provided(Y/N)
	1	NDS	200120	Pre-Stressed Tubular Spun Pole 11Mtrs Long	18140	2	NO	36280	N
	2	NDS	288302	Heat Shrinkable outdoor type cable termination kit for XLPE cable 3X95 Sq.mm	3966	4	SET	15864	N
	3	NDS	801034	Cable covering tiles 125x125x40 mm	5000	4	PK	20000	N
	4	NDS	800651	Artificial Sand/Manufacture Sand	1488	12	CMT	17856	N
	5	NDS	820672	RCC hume pipes 2000mm long 150mm dia	300	4	NO	1200	N
	6	NDS	820703	Collars for RCC hume pipe 150mm dia	80	4	NO	320	N
	7	NDS	802460	Route & joint indicating stone with M. s Anchor rod	130	4	NO	520	N
	8	NDS	768052	GI Pipes B-Class GI Pipe- 100 mm dia	1528	8	MTR	12224	N
	9	NDS	287400	11kV, 3 Core, XLPE HTUG Cable (ROUND Armoured)- 95 Sqmm	1115615	.1	KM	111561.5	N
	10	NDS	300312	LT Feeder Piller box 12 way with cutouts	62878	2	NO	125756	N
	11	NDS	300308	LT Feeder Piller box 8 way with cutouts	52399	1	NO	52399	N
	12	NDS	287212	Armoured L.T.UG Cable 1.1kV Class 120Sq.mm , 3.5 core	632811	.45	KM	284764.95	N
	13	NDS	281674	Grounding Materials for RMUs & Transformers G.I.Grounding pipe, B-Class, 40 mm dia,2.5 mtrs long, 2.9mm thick with bolts nuts,GI Strips and washers complete	770	4	NO	3080	N
	14	NDS	607054	Grounding Materials for RMUs & Transformers Good	303	4	BG	1212	N
Sι	ıbmitted by: E	BHIMANNA_	_X	Quality Salt for grounding					Page: 2



			purposes packed in 50kg gunny bags					
15	NDS	600095	Grounding Materials for RMUs & Transformers Good Quality well burnt Charcoal for grounding purposes packed in non returnable gunny bags of 30kg each	660	4	NO	2640	N
16	NDS	288322	Heat Shrinkable Straight through jointing kits for XLPE cable with Copper lugs & Al ferrules 3X95 Sq.mm	7129	2	SET	14258	N
17	NDS	289036	PVC Insulated & Un- Sheathed Aluminium Wires, Single core multi strand 1.1 kV class PVC Wire- 240 Sq.mm	334.64	100	MTR	33464	N
18	NDS	358078	SMC Street Lighting Metering Box with Automatic Control Swith, Contactors with Single Phase 5-30 Amps meter & 50/5A CT	5954	1	NO	5954	N
19	NDS	446070	LED Tube Light Fitting with Tube	1000	5	NO	5000	N
20	NDS	778025	PVC Pipe-25 mm dia	80	35	MTR	2800	N
21	NDS	357519	Measuring Equipments - LT Three phase, 4wire, CT Operated DLMS complaint ETV meter-5A, class 0.5s Accuracy	3312	1	NO	3312	N
22	NDS	303201	9KV 5kA LA Metal Oxide Ceramic type with GROUND DISCONNECTOR(Dwg No. BESCOM/GM/QS&S/26 Dtd 24.11.2018)	975	3	NO	2925	N
23	NDS	622720	Supply of PVC Insulation tape	14	20	ROLL	280	N
24	NDS	280130	Three H Frame without Transformer Seating and Seating angle support X arm for 11 mtr Spun Pole for 63/100/250/500kVA (UG Cable) - GI	18477	2	SET	36954	N
25	NDS	821900	Transparent Alkathine tube 19mm dia, 2mm thick in coils of 30 mtrs	504	3	COIL	1512	N
26 Submitted by:	NDS BHIMANNA	287207 _X	Armoured L.T.UG Cable 1.1kV Class 25 Sq.mm, 4	240813	.035	KM	8428.455	N Page: 3



			Core					
27	NDS 3	336040	L.T.Current Transformers CT Ratio-400/5A, Class-0.5 accuracy,3.75 VA, Ring type	563	4	NO	2252	N
28	NDS 3	801060	L.T.Distribution Box for 100 / 250 kVA DTC with MCCB's(SMC)	24559	1	NO	24559	N
				Sub	o Total: 827376.			
LABOR								I latitia.
S.NO	Stock Code		Item Description	Rate	Qty.Est	UOM	Amount(INR)	Utility Provided(Y/N)
1	L11KV.1.5.1	errection	of Pit 2.5 mtr depth for n of 11mtr long tubular spun per approved drawing in v Soil	1439	2	PI	2878	N
2	L11KV.2.7	Erection spun po	n of 11mtr long Concrete ble in a pit of 2.5 mtr depth, refilling with soil and	1216	2	NO	2432	N
3	_11KV.23.4.1	Heat sh	rinkable straight through joint 5 to 3x150 sq.mm HT UG	2145	.45	NO	965.25	N
4	_11KV.22.8.1		of Route Joint indicating or UG cable works.	86	4	NO	344	N
5	_11KV.22.1.1	excavat 0.75 mti mtr. incl bank up Supplyii Danger sight Ra 100mtrs	ole Work: Earth work cion for cable trench of 0.5 to r. Width and Depth upto 1 luding trial pits, depositing on oto a lead of 50 mtrs, ng and Displaying necessary Boards and Lighting, Using ails and Sign Boards at every s wherever necessary as I in Ordinary Soil	260	60	CMT	15600	N
6	L11KV.22.7	UG Cab trenches earth fro includin layers o depositi	ole Work:Refilling the cable is with selected available from trench excavation g watering, consolidation in f 15 cm. Thickness including fing of the surplus earth with a 200 Mtrs.	58	50	CMT	2900	N
7	_11KV.22.8.1	round th and wid	ing and forming with sand all ne cable to a depth of 75 mm th of 500 mm for UG cable and charges are separate).	11570	.1	KM	1157	N
8	_11KV.22.8.6	UG Cab the RC0 includin	ole Work:Laying and Jointing C pipes (100-150 mm), dia g lowering in Position: Fixing etc., Joining with mud mortor	51	4	NO	204	N
9	_11KV.22.8.1	Coverin cable w	g cable with Tiles for UG orks.	3292	.1	KM	329.2	N
10	_11KV.22.8.8	80mm to Water S fixing co	ole Work:Laying the GI Pipe o 150 mm dia at Drainage Supply Crossing including ollars elbows, bends, Tees er fitting with Cuts and	58	8	MTR	464	N
Submitted b	y: BHIMANNA_X	3.13 0.11	g Outo and					Page: 4

Amount(INR)

187814.34 28519.881 Page: 5



OTHER REQUIREMENTS:

S_EMPLOYEE Submitted by: BHIMANNA_X

Requirement

S_CONTING

BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED 150397-KAGGALIPURA OMU

WORK ORDER REPORT

		Threads wherever necessary complete.					
11	_11KV.24.1.ŧ	Making and Fixing of Heat shrinkable type pot head for 3x95 to 3x150 sq.mm HT UG Cable only	1965	6	NO	11790	N
12	_11KV.23.1.1	Laying of 3x95 to 150 sq.mm HT UG cable in Existing trench/GI pipe/Stone Ware/RCC Hume pipe using Wooden/Aluminum Rollers as directed by the departmental staff	45284	.1	KM	4528.4	N
13	L11KV.21.4	Fixing of Sheet Metal/Deep Drawn Street Lighting Metering Box with Automatic Control Swith, Contactors with Single Phase 5-30 Amps meter 50/5A CT including wiring	715	1	NO	715	N
14	L11KV.4	Construction of platform with size stone, cement concrete for erection of 500 kVA Transformer/Heavy Equipment.Construction of platform (1.5x1.5x1.2) mtr in size stone, for erection of transformers/Heavy equipment including all materials, labour. Excavation of (1.5x1.5x1) mt pit for foundation providing and laying cement concrete 1:4:8 for foundation laid in 1cm thick layers, well compacted curing etc., complete providing and construction of stone masonary 0.9m below ground level and 1.2m above ground level neatly hammer dressed in cement morter 1:6 cutting complete providing pointing to stone masonary in cement morter 1:3 after racking joint & nisely lining curing etc., plastering the concrete surfaces in cement morter 1:4 including smooth randering curing etc., curing at every stages completely.	30361	1	SC	30361	N .
15	L11KV.13.5	Fixing of GOS including wiring (11kV SB 200A)	805	6	SET	4830	N
16	L11KV.2.12	Fixing of H Frame.	242	6	NO	1452	N
17	L11KV.10.3	Fixing Metering Box for housing the ETV Meter 3-ph 4 wire along with CT's, Meter & wiring for 250 kVA TC	1449	1	SET	1449	N
18	L11KV.1.8.2.	Providing cement conccrete to 11 mtrs Spun Pole (1000x1000x2500mm) with CC 1:2:4 (without coping) [includes material and labour including necessary curing etc. (cost does not include excavation)]	14004	2	EACH	28008	N
			Sub Total	. 110707			

Item Description

Employee Cost

Contingency Charges



WORK ORDER REPORT

S_LOCALITY

ELE INSPEC S_GST Locality Allowance @ ¿.% on Labour charges (applicable for areas mentioned in Dept)

32907.555

5000 25667.89

Sub Total: 279909.6631

ATTACHMENTS:		
PERMITS: Type	Number	Acquired Date

Submitted by: BHIMANNA_X



pe: FLD REPORT Category: LAYOUT	
Attribute	Value
Adjacent Account ID	8653317812
SERVICE_POINT_ID of Adjacent Account ID*	3741020846
Date of Inspection	06-SEP-2022
Type of Layout	RESIDENTIAL
Case Id	1691236559
Total Project Area in Acres	01
Total Project Area in Guntas	26
Jurisdiction name	
Location of Premise	VGP
Site Dimesion 1	30*40
No. of Sites with Site dimension 1	4
Requested load in kW for Site Dimension1	20
Assessed load in kW for Site Dimension1	20
Site Dimesion 2	30*50
No. of Sites with Site dimension 2	6
Requested load in kW for Site Dimension2	42
Assessed load in kW for Site Dimension2	42
Site Dimesion 3	32*45
No. of Sites with Site dimension 3	15
Requested load in kW for Site Dimension3	102
Assessed load in kW for Site Dimension3	102
Site Dimesion 4	· · ·
No. of Sites with Site dimension 4	
Requested load in kW for Site Dimension4	
Assessed load in kW for Site Dimension4	-
Site Dimesion 5	
No. of Sites with Site dimension 5	
Requested load in kW for Site Dimension5	
Assessed load in kW for Site Dimension5	
Site Dimesion 6	
No. of Sites with Site dimension 6	
Requested load in kW for Site Dimension6	
Assessed load in kW for Site Dimension6	
Site Dimesion 7	
No. of Sites with Site dimension 7	
Requested load in kW for Site Dimension7	
Assessed load in kW for Site Dimension7	
Site Dimesion 8	
No. of Sites with Site dimension 8	
Requested load in kW for Site Dimension8	
Assessed load in kW for Site Dimension8	
Site Dimesion 9	
No. of Sites with Site dimension 9	
110. OF OROO WIGH ONE CHINESION O	
Requested load in kW for Site Dimensiona	
Requested load in kW for Site Dimension9 Assessed load in kW for Site Dimension9	



WORK ORDER REPORT

SERVICE HISTORY:	
Type: FLD REPORT Category: LAYOUT	
Attribute	Value
No. of Sites with Site dimension 10	
Requested load in kW for Site Dimension10	
Assessed load in kW for Site Dimension10	
Requested load for Water Supply (in HP)	
Requested load for Water Supply (in kW)	05
Requested load for Street lights (in kW)	05
Requested load for Sewage Treatment Plant (in KW)	
Requested load for Sewage Treatment Plant (in HP)	
Other Loads - MISC in KW	
Total requested load for the layout (converted in KW)	10.0
Any LT/HT/EHT line passing through the layout	
Asset id of LT/HT/EHT	
Account IDs to be surrendered*	N
Transformer Capacity in MVA	20+12.5
Peak Load of Sub Station (Amps)	130
Bank No	01
Peak Load of the Bank (Amps)	
Feeder Name*	F03-VEDA-VIGNANA
Peak Load of the feeder(Amps)	
Location of nearest DTC	
Asset id of DTC	10001620450
Capacity of the transformer	
Total connected load of DTC	
HT Voltage Regulation in %*	6
Is MT inspection required*	N
Factory Inpection required*	N
Joint inventory required*	Υ
Is Fee to be charged for dry type transformer, if proposed	N
Cable precommissioning test and charges required*	N
RMU pre commissioning test and Charges required*	N
LBS pre commissioning test and Charges required*	N
Supervision Charges required	Υ
Decommisioning of Assets required	N
Additional Documents Required, please specify	
Whether space provided for sub station (y / n)	
Any other details	

Submitted by: BHIMANNA_X

Requestor Name:

Date:



WORK ORDER REPORT

COMPLETION COMMENTS:			
	_		_
Start Date:	Time:	Completion Date:	Time:
FAILURE CODES:			
Failure:	Repair:	Component:	
Follow-up Action Required:			

SUMMARY

TASK NO	MATERIAL	LABOR	OTHER REQT	TOTAL
01	827375.905	110406.85	279909.6631	1217692.4181
OVERALL TOTAL	827375.905	110406.85	279909.6631	1217692.4181