



ಬೆಂಗಳೂರು ವಿದ್ಯುತ್ ಸರಬರಾಜು ಕಂಪನಿ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸಂಪೂರ್ಣ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಪತ್ರ ಸಂಖ್ಯೆ: ಕಾನಿಇಂ(ವಿ)/ಕೆಂವಿ/ಸಕಾಇಂ(ಕ)/ಕೆಇಂ(ತಾಂ)/22-23/

ದಿನಾಂಕ: 31 JAN 2023

8408-09

ಲಗತ್ತು:

ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್ (ವಿ) ರವರ ಕಛೇರಿ,
ಕೆಂಗೇರಿ ವಿಭಾಗ, ಮೈಸೂರು ರಸ್ತೆ,
ಕೆಂಗೇರಿ, ಬೆಂಗಳೂರು - 560060
ಮೊ: 94498 77033
ಈ ಮೇಲ್: eekengeri.work4@gmail.com.

ಗೆ,

ಶ್ರೀ.ಪ್ರಸನ್ನ ಕುಮಾರ್.ಕೆ,

ಸರ್ವೇ ನಂ.253/2, ಕಂಬೀಪುರ ಗ್ರಾಮ,

ಕೆಂಗೇರಿ ಹೋಬಳಿ, ಬೆಂಗಳೂರು.

ಮಾನ್ಯರೆ,

ವಿಷಯ: ಶ್ರೀ.ಪ್ರಸನ್ನ ಕುಮಾರ್.ಕೆ, ಸರ್ವೇ ನಂ.253/2, ಕಂಬೀಪುರ ಗ್ರಾಮ, ಕೆಂಗೇರಿ ಹೋಬಳಿ, ಬೆಂಗಳೂರು ರಲ್ಲಿ ನಿರ್ಮಿಸಲು ಉದ್ದೇಶಿಸಿರುವ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಬಡಾವಣೆಗೆ 234 ಕಿ.ವ್ಯಾ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನೀಡಲು ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ (NOC) ನೀಡುವ ಬಗ್ಗೆ.

ಉಲ್ಲೇಖ: 1. ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್ (ವಿ), ಕೆ-1 ಉಪ ವಿಭಾಗ ರವರ ಪತ್ರ ಸಂಖ್ಯೆ: ಸಕಾಇಂ(ವಿ)ಕೆ-1/ಸಇ (ತಾಂ)/22-23/6211/31.01.2023.

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಸರ್ವೇ ನಂ.253/2, ಕಂಬೀಪುರ ಗ್ರಾಮ, ಕೆಂಗೇರಿ ಹೋಬಳಿ, ಬೆಂಗಳೂರು ರಲ್ಲಿ ನಿರ್ಮಿಸಲು ಉದ್ದೇಶಿಸಿರುವ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಬಡಾವಣೆಗೆ 234 ಕಿ.ವ್ಯಾ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನೀಡಲು ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ(NOC)ಯನ್ನು ಈ ಕೆಳಕಂಡ ನಿಬಂಧನೆಗಳಿಗೊಳಪಟ್ಟು ನೀಡಲಾಗಿದೆ.

- 1) ನಿಮ್ಮ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಸಮುಚ್ಚಯಕ್ಕೆ ಹಾಲಿ ಕುಂಬಳಗೂಡು 66/11 ಕೆವಿ ವಿದ್ಯುತ್ ಉಪಕೇಂದ್ರದಿಂದ ಸ್ವಕಾಮಗಾರಿ ಅಡಿಯಲ್ಲಿ ಹಾಲಿ ಇರುವ ಎಫ್-10 ಫೀಡರ್ ಅನ್ನು 800 ಮೀ 3*95sqmm ಹೆಚ್.ಟಿ ಯು.ಜಿ ಕೇಬಲ್ ಬಳಸಿ 3ವೇ ಆರ್.ಎಂ.ಯು ಮತ್ತು 1*250 ಕೆವಿಎ ತ್ರೈಲಸಹಿತ ಪರಿವರ್ತಕವನ್ನು ಗ್ರಾಹಕರ ಆವರಣದಲ್ಲಿ ಅಳವಡಿಸಿ ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ನೀಡಲು ಪ್ರಸ್ತಾವಿಸಲಾಗಿದೆ.
- 2) 11 ಕೆವಿ ಮತ್ತು ಇತರ ಮೂಲಸೌಕರ್ಯಗಳನ್ನು ಕಲ್ಪಿಸುವ ಪರ್ಯಾಯ ಮಾರ್ಗದ ಕೆಲಸವನ್ನು ಸರ್ಕಾರದ ಅನುಮತಿ ಪಡೆದ ಒಂದನೇ ದರ್ಜೆ ಗುತ್ತಿಗೆದಾರರಿಂದ, ಸ್ವಯಂ ಕಾರ್ಯ ಯೋಜನೆಯಡಿಯಲ್ಲಿ ಮೇಲ್ವಿಚಾರಣಾ ಶುಲ್ಕಗಳನ್ನು ಪಾವತಿಸಿ ನಿರ್ವಹಿಸಬೇಕು.
- 3) ನಿಮ್ಮ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಉದ್ದೇಶಕ್ಕೆ ಹೆಚ್ಚುವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜನ್ನು ಅರ್ಜಿ ಸಲ್ಲಿಸುವಾಗ ಇರುವ ಬಿ.ವಿ.ಕಂ. ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಯಮಗಳ ಪ್ರಕಾರ ನೀಡಲಾಗುವುದು.
- 4) ನಿಮ್ಮ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಉದ್ದೇಶಕ್ಕೆ ಬಿ.ವಿ.ಕಂ. ಮಾರ್ಗ ಹಾದುಹೋಗಿದ್ದರೆ, ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಪಡೆಯುವ ಮುನ್ನ ಅವುಗಳನ್ನು ನಿಮ್ಮ ಸ್ವಂತ ಖರ್ಚಿನಲ್ಲಿ ಆವರಣದ ಹೊರಗೆ ಸ್ಥಳಾಂತರಿಸಬೇಕು.

- 5) ಸಿಮ್ಲಾ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಉದ್ದೇಶಕ್ಕೆ ಇ.ಹೆಚ್.ಟಿ. ಮಾರ್ಗವು ಹಾದುಹೋಗಿದ್ದಲ್ಲಿ, ವಿದ್ಯುತ್ ಸಂಪರ್ಕ ಪಡೆಯುವ ಮುನ್ನ ಸಂಬಂಧಪಟ್ಟ ಪ್ರಾಧಿಕಾರದಿಂದ ಪ್ರತ್ಯೇಕ ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ (NOC) ಪಡೆಯಬೇಕು ಮತ್ತು IE ನಿಯಮದ ಪ್ರಕಾರ ಸೂಕ್ತ ಕಾರಿಡಾರ್ ಲಬ್ಯವಿರುವಂತೆ ನೋಡಿಕೊಳ್ಳಬೇಕು.
- 6) ಈ ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ (NOC) ವನ್ನು ತಮ್ಮ ಕೋರಿಕೆಯಂತೆ ನಕ್ಷೆ ಮಂಜೂರಾತಿಗಾಗಿ ನೀಡಲಾಗಿದೆಯೇ ಹೊರತು, ಬಿ.ವಿ.ಕಂ. ವತಿಯಿಂದ ವಿದ್ಯುತ್ ಸರಬರಾಜಿನ ಕರಾರು ಅಲ್ಲ. ವಿದ್ಯುತ್ ಸರಬರಾಜಿಗಾಗಿ ಅರ್ಜಿ ಸಲ್ಲಿಸುವಾಗ ಇರುವ KERC ಮತ್ತು ಬಿ.ವಿ.ಕಂ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಯಮಗಳ ಪ್ರಕಾರ ನೀಡಲಾಗುವುದು.
- 7) ಈ ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ (NOC) ನೀಡಿಕೆಯಿಂದ ಉದ್ಭವವಾಗುವ ಯಾವುದೇ ವಿವಾದಗಳಿಗೆ ಬಿ.ವಿ.ಕಂ. ಜವಾಬ್ದಾರಿಯಾಗಿರುವುದಿಲ್ಲ.
- 8) ಸಿಮ್ಲಾ ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಸಮುಚ್ಚಯದಲ್ಲಿ ವಿದ್ಯುತ್ ಸರಬರಾಜಿಗಾಗಿ ಅರ್ಜಿ ಸಲ್ಲಿಸುವಾಗ, ಈ ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ (NOC) ವನ್ನು ಜೊತೆಯಲ್ಲಿ ಸಲ್ಲಿಸಬೇಕು.
- 9) ಈ ನಿರಾಪೇಕ್ಷಣಾ ಪತ್ರ (NOC) ದ ಅವಧಿಯು, ಈ ಪತ್ರದ ದಿನಾಂಕದಿಂದ ಎರಡು ವರ್ಷಗಳವರೆಗೆ ಚಾಲ್ತಿಯಲ್ಲಿರುತ್ತದೆ.
- 10) ಕಾರ್ಯ ವ್ಯವಹರಣಾ ಶುಲ್ಕವಾಗಿ 5900/-ರೂ. ಗಳನ್ನು ರಸೀದಿ ಸಂಖ್ಯೆ 437618704082 ದಿನಾಂಕ: 31.01.2023 ರ ಮೂಲಕ ಪಾವತಿಸಿಕೊಳ್ಳಲಾಗಿದೆ.
- 11) ಪ್ರಸ್ತಾವಿತ ವಸತಿ ಸಮುಚ್ಚಯದಲ್ಲಿ ಬಿ.ವಿ.ಕಂ. ಸ್ಥಾವರಗಳೇನಾದರೂ ಇದ್ದರೆ, 11 ಕೆವಿ ಮೂಲ ಸೌಕರ್ಯಗಳ ಕೆಲಸವನ್ನು ಪ್ರಾರಂಭಿಸುವುದಕ್ಕಿಂತ ಮುಂಚೆ ಸರಂಡರ್ ಮಾಡಬೇಕು

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್ (ವಿ).,

ಕೆಂಗೇರಿ ವಿಭಾಗ, ಬಿ.ವಿ.ಕಂ, ಬೆಂಗಳೂರು-60.

ಪ್ರತಿ.

1. ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರ್(ವಿ), ಕೆ-1 ಉಪ ವಿಭಾಗ, ಕೆಂಗೇರಿ, ಬೆಂಗಳೂರು ರವರಿಗೆ ಕಡತದೊಂದಿಗೆ ಮಾಹಿತಿಗಾಗಿ.
2. ಕೆ.ಇಂ(ತಾ)/ಮು.ಕ.



Bangalore Electricity Supply Company Limited

No: BESCOM/LYT_PWRSN/6398451471/13-03-2023

9983

GSTIN Number: 29AACCB1412G1Z5

17032023

16 MAR 2023

Lyt-28

22.23

Office of

Superintendent Engineer
SuperIntending Engineer (Ele)
K1 KENGERI, BESCOM,
BESCOM, West Circle

DATE: 13-03-2023
Bengaluru

To,

K PRASANNA KUMAR,

SY NO 253/12, KAMBIPURA VILLAGE KENGERI HOBLI

BENGALURU SOUTH

IND 560059

Sir/Madam,

Sub: Electrification of Residential Layout

Ref: 1) Application No:009910748020 Dated: 04-JAN-2023

2) Account ID : 8977379634

3) Prevailing KERC regulations.

With reference to the above, approval is hereby accorded for electrification of proposed Layout to an extent of 234 kW on Account ID 8977379634, subject to the following:

1. You are requested to pay the following charges by Cash/ DD (above 10000/-, only DD will be accepted) in favour of The Assistant Executive Engineer (EI) K1 KENGERI, BESCOM within 30 days from the date of this letter, failing which the sanction will lapse.

Sl.No	Particulars	Amount	CGST	SGST	Total Amount
1.	10% supervision charges on estimate Cost	₹310077	₹27907	₹27907	₹365891
Total					₹365891.00

- You have to carry out the works **under self-execution** as per the estimate prepared by **BESCOM** through a Licensed Electrical contractor holding valid Class 1 license.
- The materials use shall confirm to specifications wherever necessary.
- The entire distribution system with the connected equipments will be taken over by **BESCOM** after completion of the works.
- If the cost of the materials excess Rs. 1.00 Lakhs (i.e. DTC's Conductor, Poles, Cables, RMU etc..) should be jointly inspected by TA&QC staff and the representative of consumer at the manufacturing site before delivery of materials to the work spot.
- All the major materials like transfer, Switchgear, ACSR Conductor (more than 1 Kms) Metering cubicle, HT UG cable, LT UG cable, 11 KV Pin insulators and 11 KV Single/Double break GOS shall be procured by the agencies only from authorized dealers of approved vendors to **BESCOM**.
- Guarantee shall be furnished for a period of not less than one year for the materials used in the works as well as for the quality of the work carried out from the date of taking over of the lines and equipment's by **BESCOM**.
- Proof of having purchased the materials used for executing the works from the **BESCOM** Vendor approved firm will be verified wherever necessary.
- After payment of supervision charges, administrative approval will be issued from this Office and work order will be issued by the **Executive Engineer, (El.) C,O&M, K1 KENGERI, BESCOM**.
- An Agreement on Rs. 200.00 Stamp paper shall be executed to maintain the lines and transformer centers erected in the layout till 25% of the applicant avail power supply in the layout and also to maintain the LT UG cable system.
- For residential buildings Solar Water heater should be provided with a capacity of 100 liters to individual house of suitable capacity i.e. 100 liters per house.
- Site details are as follows:

S. No.	Site Dimension	No. of sites with given Site dimension	Requested load for given site dimension
1	30*40	7	35
2	30*20	6	18
3	30*50	24	168

Total Project Area in Acres: 1

Total Project Area in Guntas: 38

2. The **PROPOSED** Sanctioned Load details of your Layout are as follows:

S. No.	Type of Loads requested	Requested Load
1	Requested load for Water Supply (in kW)	
2	Requested load for Water Supply (in HP)	7.5
3	Requested load for Street lights (in kW)	2
4	Requested load for Sewage Treatment Plant (in kW)	
5	Requested load for Sewage Treatment Plant (in HP)	
7	Miscellaneous Load (in kW)	227
8	Total requested load for the layout (converted in kW)	234

You are requested to contact the undersigned in case of any other information that may be required by you.

We remain at your services.

The following charges in Rs are also payable along with the 10% Supervision charges mentioned below:

- | | | |
|-------------------------------------|---|-------------|
| 1. DCW Estimate cost | : | 5,83,445.00 |
| 2. One time maintenance cost | : | 1,84,211.00 |
| 3. GST on One time maintenance cost | : | 33,158.00 |

Yours faithfully

Superintendent Engineer
superintending Engineer (Ele)
BESCOM
Bengaluru