7.0 Facilities Proivded in 1 BHK

1. Room dimensions : Asper NBC

2. Stairs Riser : 125 mm

3. Stairs Tread : 250 mm

4. Stair Case Railings : MS 50 mm X 50 mm

Square pipe Hand rail (main) with 25 X 25 mm MS Square tube inside.

5. Loft - 600 mm wide : Kitchen & Bed

6. Calling Bell : 1

7. Toilet : With European closets,

one number in 1 BHK and one

more attached in 2 BHK unit.

9. Wash Basin : 1 for 1 BHK

: 2 for 2 BHK

10. Kitchen Slab

[0.6m Wide, 40mm thick]: Granite

Kitchen Sink

[without Drain boarad]

[0.60m X 0.60m] : 1 - Steel

12. Door Frame :

Main Door [Red] : Sal wood

RCC : Bed & Utility
PVC(Approved quality) : Bath & Toilet

Shutters 13.

Flush [30 mm thick]

Main door, Bed &

Utility

PvC Shutter

Bath & W.C.

Aluminium

Windows 14.

[with Guard bars]

Powder coated

2 track/UPvC

Flooring 15.

Living, Bed,

Kitchen and Utility.

: Vitrified Tiles

Bath & Toilet [Antiskid]

: Ceramic Tiles

Staircase, steps

& Common areas

: Tandur Blue stones

Dadooing [Ceramic Tiles] 16.

Bath Room

Upto 2.00m

Toilet

Upto 1.20m

Kitchen

Upto 0.60m

[Above platform]

Floor to Floor Height 17.

Min 3m

Electrical [Points only] 18.

Heating Points [5pin]

2

Lighting Points

8 for 1 BHK

9 for 2 BHK

3 for 1 BHK

Socket Points [5 pin]

4 for 2 BHK

Ceiling Fan point

2 for 1 BHK

3 for 2 BHK

19. Taps : 4 for 1 BHK

[2 Long body for Kitchen

& Bath]

5 for 2 BHK

[3 Long body for Kitchen

& Bath]

20. Sanitary Pipes : PvC -u @ 6Kg/ as

per design

21. Painting

Internal Walls : OBD

External Walls : Water Cement

Doors : Enamel

22. Over Head Tanks : PvC/Synthetic

23. Solar Lighting : Common areas

24. Water Proofing : Bath, Toilet,

Sump & Terrace

8.0 Facilities Provided:

a. Rain Water Harvesting

i. Roof Water Harvesting

ii. Ground Water Recharge

b. Sewage Treatment

c. Roads & Culverts

d. Storm Water Drains

e. Lay out Electrification

f. Sump Tank for each block

g. Solar Lighting for Street Lights

h. Arboriculture

j. Housing [G+3] : As Per local ZR

k. Parks
1. Civic Amenities
n. Open area
i. As Per local ZR
i. As Per local ZR
i. As per local ZR

Note: All the Components are confirming to BIS and Specific type/brand and further specifications

of itmes are to be got approved by Engineer in

Charge of the Project.